

Issued for Construction - Lyric Theatre - Material Schedule

0. All Interior finishes shall comply with Table 803.3, SBC 801
1. All reference manufacturers, brands and products are representative of the design intent as referenced in the design drawings, specifications, schedules and reports. They may be substituted under a Contractor's Proposal provided that they are accepted by the
2. All divergence from the reference products/ materials are to be formally notified in writing to the designer. The Designer shall have not less than 10 working days to respond to all proposals. The Designer reserves the right to reject the proposed alternative
3. All suggested alternative samples are to be issued to the Designer for review at least 10 working days prior to the submission of a formal Contractor's Proposal. Acceptance of the sample by the Designer does not relieve the Contractor of conformance of the installation
4. Image swatches are indicative only and are not to be used for colour matching, sampling, or benchmarking.
5. Refer to the design drawings for locations of finishes.



Date

Rev.Date
Rev. No.



31.1.2024

31.1.2024
FOO

LYRIC THEATRE - Material Schedule

TYPE	NAME	RVT	DRAWING	visible	material	density / acoustic requirement	description	treatment/color	picture	contact
WALLS	BACK WALLS - SOLID CURVED W. TEXTURE	AW10	BACK WALLS - SOLID CURVED W. TEXTURE ACOUSTIC WALL, SOLID WOOD, ASH THICKNESS MIN. 55 MM + 10-30 MM TEXTURE MOUNTED ON STEEL SUBSTRUCTURE TO BE CALCULATED BY CONTRACTOR DENSITY MIN. 30 KG/M2 FOR TOTAL BUILD-UP CNC CUT TEXTURE ACC. TO 3D MODEL FINISH: FIRE TREATED TO FIRE CLASS C ACC. ASTM E84, 100% TRANSPARENT VARNISH, ULTRAMATTE, GLOSS 2	AR-014130 (principle)	yes	Ash wood. Solid.. Mounted on steel structure according to contractor	min 30 kg / m2 55mm deep minimum. Numeric control cut per architectural design . CNC Cut Texture acc. to 3D model Any deviation from the design affecting opening ratio, size or distribution of solid elements to be submitted to acoustician for review and approval All layers must be bonded to the structure tightly and continuously into one solid monolithic body, with no air gaps or bubbles between layers. The resulting complex should achieve a surface density of min 30kg/m2	Fire retardant treated to class C, 100 % transparent Varnish, ultra matte, gloss 2 Treatment: 2 times lacquer type AB19. Clear lacquer, gloss 5 1 time finish lacquer, clear, ultramatte, gloss 2.		JJI Inventar JJi Akustik & Inventar A/S info@jji.as +45 4483 0208 Baltorpbakken 5 DK-2750 Ballerup https://www.jji.as/in-sign-akustik Contact person: Janna Linn Grunth <jlg@jji.as>
	BACK WALLS - SOLID CURVED NO TEXTURE	AW10B	BACK WALLS - SOLID CURVED NO TEXTURE ACOUSTIC WALL, SOLID WOOD, ASH THICKNESS MIN. 55 MM MOUNTED ON STEEL SUBSTRUCTURE TO BE CALCULATED BY CONTRACTOR DENSITY MIN. 30 KG/M2 FOR TOTAL BUILD-UP FINISH: FIRE TREATED TO FIRE CLASS C ACC. ASTM E84, 100% TRANSPARENT VARNISH, ULTRAMATTE, GLOSS 2	AR-014130 (principle)	yes	Ash wood. Solid.. Mounted on steel structure according to contractor	min 30 kg / m2 55mm deep minimum. Numeric control cut per architectural design. CNC Cut Texture acc. to 3D model All layers must be bonded to the structure tightly and continuously into one solid monolithic body, with no air gaps or bubbles between layers. The resulting complex should achieve a surface density of min 30kg/m2	Fire retardant treated to class C, 100 % transparent Varnish, ultra matte, gloss 2 Treatment: 2 times lacquer type AB19. Clear lacquer, gloss 5 1 time finish lacquer, clear, ultramatte, gloss 2.		JJI Inventar JJi Akustik & Inventar A/S info@jji.as +45 4483 0208 Baltorpbakken 5 DK-2750 Ballerup https://www.jji.as/in-sign-akustik Contact person: Janna Linn Grunth <jlg@jji.as>
	ACOUSTIC WALL, SOLID WOOD, ASH	AW19	ACOUSTIC WALL, SOLID WOOD, ASH THICKNESS MIN. 55 MM MOUNTED ON STEEL SUBSTRUCTURE TO BE CALCULATED BY CONTRACTOR EMBEDDED CURTAIN DOORS WITH CONCEALED HINGES DENSITY MIN. 30 KG/M2 FOR TOTAL BUILD-UP FINISH: FIRE TREATED TO FIRE CLASS C ACC. ASTM E84, 100% TRANSPARENT VARNISH, ULTRAMATTE, GLOSS 2	AR-014130 (principle)	yes	Ash wood. Solid. Mounted on steel structure according to contractor	min 30 kg / m2 55mm deep minimum. All layers must be bonded to the structure tightly and continuously into one solid monolithic body, with no air gaps or bubbles between layers. The resulting complex should achieve a surface density of min 30kg/m2	Fire retardant treated to class C, 100 % transparent Varnish, ultra matte, gloss 2 Treatment: 2 times lacquer type AB19. Clear lacquer, gloss 5 1 time finish lacquer, clear, ultramatte, gloss 2.		JJI Inventar JJi Akustik & Inventar A/S info@jji.as +45 4483 0208 Baltorpbakken 5 DK-2750 Ballerup https://www.jji.as/in-sign-akustik Contact person: Janna Linn Grunth <jlg@jji.as>
	BACK WALLS - ACOUSTICALLY TRANSPARENT	AW11	BACK WALLS - ACOUSTICALLY TRANSPARENT ACOUSTICALLY TRANSPARENT WALL, ASH VENEER ON BIRCH PLYWOOD THICKNESS 18 MM PLYWOOD WITH ASH VENEER MOUNTED ON 45X25 WOODEN FRAMES, STEEL SUBSTRUCTURE TO BE CALCULATED BY CONTRACTOR OPENING RATIO APPROX. 60% CNC CUT TEXTURE / OPENINGS ACC. TO 3D MODEL FINISH: FIRE TREATED TO FIRE CLASS C ACC. ASTM E84, 100% TRANSPARENT VARNISH, ULTRAMATTE, GLOSS 2	AR-014131 (principle)	yes	Birch plywood, ash wood veneer.Mounted on steel structure according to contractor	50% min. opening for acoustic transparency. 50% opening for acoustic transparency. CNC Cut Texture acc. To 3D model veneer slicing : crown cut veneer mixing: mix. reverse slip matched. varying number of flitches per panel with one order : 3 to 6 Any deviation from the design affecting opening ratio, size or distribution of solid elements to be submitted to acoustician fore review and aproval all elements to be fixed tightly and contacts to be treated with soft non-porous material to prevent rattling and vibrations	Fire retardant treated to class C, 100 % transparent Varnish, ultra matte, gloss 2 Treatment: 2 times lacquer type AB19. Clear lacquer, gloss 5 1 time finish lacquer, clear, ultramatte, gloss 2.		JJI Inventar JJi Akustik & Inventar A/S info@jji.as +45 4483 0208 Baltorpbakken 5 DK-2750 Ballerup https://www.jji.as/in-sign-akustik Contact person: Janna Linn Grunth <jlg@jji.as>
	Acoustic Wall, Solid GRC	AW12A AW12B AW12C	Acoustic Wall, Solid GRC THICKNESS MIN. 15 MM (MIN. 30KG/M2) ELEMENTS WITH TOUNGUE AND GROOVE CONNECTIONS MOUNTED ON STEEL SUBSTRUCTURE TO BE CALCULATED BY CONTRACTOR TYPE A: ZIGZAG SHAPE WITH VAR. ANGLES ACC. TO POSITION TYPE B: BUBBLE SHAPE VERTICAL WALL TYPE C: BIG BUBBLE SHAPE	AR-014131 (principle)	(no)	GRC Fiber Cement elements Solid wall, Fibre concrete with custom geometry. Mounted on concrete walls and/or steel structure according to contractor	min 30kg/m2 fiber concrete elements mounted on steel frame construction according to contractor .	Grey, RAL 7023, BBF No. 96-S		BB Fiberbeton / Fiber concrete www.bbfiberbeton.dk/en https://www.bbfiberbeton.dk/en/contact Contact person: Helene Bieger helene@bbfiberbeton.dk
Parterre Walls - Stalls	AW13	Parterre Walls - Stalls TOP: ACOUSTIC WALL, SOLID WOOD, ASH THICKNESS MIN. 55 MM + 10-30 MM TEXTURE MOUNTED ON STEEL SUBSTRUCTURE TO BE CALCULATED BY CONTRACTOR MIN. 30 KG/M2 FOR TOTAL BUILD-UP CNC CUT TEXTURE ACC. TO 3D MODEL FINISH: FIRE TREATED TO FIRE CLASS C ACC. ASTM E84, 100% TRANSPARENT VARNISH, ULTRAMATTE, GLOSS 2 BOTTOM: ACOUSTICALLY TRANSPARENT WALL FINISH (AS TYPE AW11), ASH VENEER ON BIRCH PLYWOOD THICKNESS 18 MM PLYWOOD WITH ASH VENEER WITH FELT BACK MOUNTED ON 45X25 WOODEN FRAMES, 45 MM MINERAL WOOL FILLING (DENSITY 60 KG/M³) STEEL SUBSTRUCTURE TO BE CALCULATED BY CONTRACTOR 60% OPENING RATIO (TO ACOUSTICALLY TRANSPARENT) CNC CUT TEXTURE / OPENINGS ACC. TO 3D MODEL FINISH: FIRE TREATED TO FIRE CLASS C ACC. ASTM E84, 100% TRANSPARENT VARNISH, ULTRAMATTE, GLOSS 2 VISIBLE BACK (SEAT SIDE): ASH VENEER ON BIRCH PLYWOOD THICKNESS 18MM PLYWOOD WITH VENEER 25 MM HATPROFILES, SPACERS FINISH: FIRE TREATED TO FIRE CLASS C ACC. ASTM E84, 100% TRANSPARENT VARNISH, ULTRAMATTE, GLOSS 2	AR-014151	yes	Front: Ash wood. Solid. Mounted on concrete walls and/or steel structure according to contractor Back: Birch plywood, ash wood veneer. Mounted on steel structure according to contractor	TOP: min 30 kg / m2 BOTTOM: 50% acoustically transparant Top/Front: 55mm deep minimum. Numeric control cut per architectural desing CNC Cut Texture acc. To 3D model Bottom/Back: 50% opening for acoustic transparency. CNC Cut Texture acc. To 3D model veneer slicing : crown cut veneer mixing: mix. reverse slip matched. varying number of flitches per panel with one order : 3 to 6 Any deviation from the design affecting opening ratio, size or distribution of solid elements to be submitted to acoustician fore review and aproval All layers must be bonded to the structure tightly and continuously into one solid monolithic body, with o air gaps or bubbles between layers. The resulting complex should achieve a surface density of min 30kg/m2. The minimum weights per unit area should be achieved at all points on the surfaces. For textured surfaces, this means the minimum should be met at the deepest depressions, where material (or assembly) is the thinnest.	Fire retardant treated to class C, 100 % transparent Varnish, ultra matte, gloss 2 Treatment: 2 times lacquer type AB19. Clear lacquer, gloss 5 1 time finish lacquer, clear, ultramatte, gloss 2. All substructure behind transparent parts to be painted NCS 8500-N			

Issued for Construction - Lyric Theatre - Material Schedule

0. All Interior finishes shall comply with Table 803.3, SBC 801
1. All reference manufacturers, brands and products are representative of the design intent as referenced in the design drawings, specifications, schedules and reports. They may be substituted under a Contractor's Proposal provided that they are accepted by the
2. All divergence from the reference products/ materials are to be formally notified in writing to the designer. The Designer shall have not less than 10 working days to respond to all proposals. The Designer reserves the right to reject the proposed alternative
3. All suggested alternative samples are to be issued to the Designer for review at least 10 working days prior to the submission of a formal Contractor's Proposal. Acceptance of the sample by the Designer does not relieve the Contractor of conformance of the installation
4. Image swatches are indicative only and are not to be used for colour matching, sampling, or benchmarking.
5. Refer to the design drawings for locations of finishes.



Date

Rev.Date
Rev. No.



31.1.2024

31.1.2024
FOO

LYRIC THEATRE - Material Schedule

TYPE	NAME	RVT	DRAWING	visible	material	density / acoustic requirement	description	treatment/color	picture	contact
	CURTAIN BOX COVER AT GALERIES 70MM	AW13 A	15MM - PLYWOOD (BLACK) AHDESIVE 15MM - PLYWOOD (BLACK) RHS PROFILE FRAME CONNECTED TO GALERIES ACCORDING TO CONTRACTOR FINISH: FIRE TREATED TO FIRE CLASS C WEIGHT MIN 15KG/M2	AR-015004	yes	plywood	min 15 kg / m2			
	Risers in balcony - behind seating	AW14	Front: Ash veneer on Birch plywood FRONT: VENEERED PLYWOOD, CURVED AS SHOWN IN PLANS MIN. 45 MM TOTAL THICKNESS (MIN. DENSITY 30 KG/M2) BUILT-UP BY MULTIPLE BEND LAYERS, GLUED TOGETHER FOR FULL DENSITY. PLACED ON STUDS.	AR-015573	yes	Birch plywood, ash wood veneer	min 30 kg / m2	Veneered plywood with insulation in the cavity veneer slicing : crown cut veneer mixing: mix. reverse slip matched. varying number of flitches per panel with one order : 3 to 6 All layers must be bonded to the structure tightly and continuously into one solid monolithic body, with no air gaps or bubbles between layers. The resulting complex should achieve a surface density of min 30kg/m2		JJI inventar JJi Akustik & Inventar A/S info@jji.as +45 4483 0208 Baltorpbakken 5 DK-2750 Ballerup https://www.jji.as/in-sign-akustik Contact person: Janna Linn Grunth <jlg@jji.as>
	Other Walls - Partition Walls / VIP behind seating	AW15	Partition Walls / VIP behind seating Front: Solid wood, Ash PARTITION WALLS - VIP BEHIND SEATING FRONT: SOLID WOOD, ASH THICKNESS MIN. 55 MM + 10-30 MM TEXTURE CNC CUT TEXTURE / OPENINGS ACC. TO 3D MODEL L- PROFILES, MOUNTED ON SUBSTRUCTURE FOR CLT/BALCONY STEEL SUBSTRUCTURE TO BE CALCULATED BY CONTRACTOR MIN. 30 KG/M2 FOR TOTAL BUILD-UP FINISH: FIRE TREATED TO FIRE CLASS C ACC. ASTM E84, 100% TRANSPARENT VARNISH, ULTRAMATTE, GLOSS 2 VISIBLE BACK (SEAT SIDE): ASH VENEER ON BIRCH PLYWOOD THICKNESS 18MM PLYWOOD WITH VENEER 25 MM HATPROFILES, SPACERS FINISH: FIRE TREATED TO FIRE CLASS C ACC. ASTM E84, 100% TRANSPARENT VARNISH, ULTRAMATTE, GLOSS 2	AR-015004 AR-015571	yes	Solid ash wood, mounted on steel structure according to contractor	min 30 kg / m2	55mm deep minimum. CNC Cut Texture acc. To 3D model Any deviation from the design affecting opening ratio, size or distribution of solid elements to be submitted to acoustician fore review and aproval All layers must be bonded to the structure tightly and continuously into one solid monolithic body, with o air gaps or bubbles between layers. The resulting complex should achieve a surface density of min 30kg/m2. The minimum weights per unit area should be achieved at all points on the surfaces. For textured surfaces, this means the minimum should be met at the deepest depressions, where material (or assembly) is the thinnest.		JJI inventar JJi Akustik & Inventar A/S info@jji.as +45 4483 0208 Baltorpbakken 5 DK-2750 Ballerup https://www.jji.as/in-sign-akustik Contact person: Janna Linn Grunth <jlg@jji.as>
	Control room - Outside Finish (Hall side)	AW16	Control room Wall - exterior finish: Ash veneer on Birch plywood CONTROL ROOM - OUTSIDE FINISH (HALL SIDE) FRONT: VENEERED PLYWOOD, CURVED AS SHOWN IN PLANS MIN. 45 MM TOTAL THICKNESS (MIN. DENSITY 30 KG/M2) BUILT-UP BY MULTIPLE BEND LAYERS, GLUED TOGETHER FOR FULL DENSITY. PLACED ON STUDS.	AR-014170	yes	Birch plywood, ash wood veneer, mounted on steel structure according to contractor	min 30 kg / m2	Front: Numeric control cut per architectural desing veneer slicing : crown cut veneer mixing: mix. reverse slip matched. varying number of flitches per panel with one order : 3 to 6 All layers must be bonded to the structure tightly and continuously into one solid monolithic body, with no air gaps or bubbles between layers. The resulting complex should achieve a surface density of min 30kg/m2		JJI inventar JJi Akustik & Inventar A/S info@jji.as +45 4483 0208 Baltorpbakken 5 DK-2750 Ballerup https://www.jji.as/in-sign-akustik Contact person: Janna Linn Grunth <jlg@jji.as>
	Backwall / Control room	IW46	21 MM PERFORATED PLYWOOD, MOUNTED WITH BLACK SCREWS TOTAL THICKNESS: 96 MM 21 MM PERFORATED PLYWOOD PAINTED BLACK, MOUNTED WITH BLACK SCREWS MIN. 30% OPEN PERFORATION, ø5mm holes 50 MM ACOUSTIC ABSORPTION (Medium density mineral wool -20-60 kg/m³) 25MM ALUMINUM HAT PROFILES, 300 MM C/C TOTAL BUILD-UP TO ACHIEVE SOUND ABSORPTION CLASS A	AR-014170	yes	PERFORATED PLYWOOD mounted on studs	Class A absorption	HOLE DIAMETER: Ø 5 MM SPACING: 16MM ALIGN (X/Y) 50 MM ACOUSTIC INSULATION / STUD 25MM ALUMINUM HAT PROFILES, 300 MM C/C		kvadratacoustics@kvadrat.org
	walls in control room - towards hall	LW14	Special Steel structure framing with gypsum. Min. Rw 55db Thickness 425 mm 2 x 12,5 mm gypsum 1 x 12 mm plywood 95 mm C-profiles Steel substructure for windows / Gap between c- profiles (min. 6 mm) 95 mm C-profiles 1 x 12 mm plywood 2 x 12,5 mm gypssum	AR-014170	no	Gypsum wall including metal studs etc. Built as double wall due to acoustic demand	> Rw 55dB	Gypsum wall including metal studs etc. Built as double wall due to acoustic demand		

Issued for Construction - Lyric Theatre - Material Schedule

0. All Interior finishes shall comply with Table 803.3, SBC 801
1. All reference manufacturers, brands and products are representative of the design intent as referenced in the design drawings, specifications, schedules and reports. They may be substituted under a Contractor's Proposal provided that they are accepted by the
2. All divergence from the reference products/ materials are to be formally notified in writing to the designer. The Designer shall have not less than 10 working days to respond to all proposals. The Designer reserves the right to reject the proposed alternative
3. All suggested alternative samples are to be issued to the Designer for review at least 10 working days prior to the submission of a formal Contractor's Proposal. Acceptance of the sample by the Designer does not relieve the Contractor of conformance of the installation
4. Image swatches are indicative only and are not to be used for colour matching, sampling, or benchmarking.
5. Refer to the design drawings for locations of finishes.



Date

Rev.Date
Rev. No.



31.1.2024

31.1.2024
FOO

LYRIC THEATRE - Material Schedule

TYPE	NAME	RVT		DRAWING	visible	material	density / acoustic requirement	description	treatment/color	picture	contact
	walls in control room - towards sides	LW12	Gypsum wall, db studded. Min. Rw 55db Thickness 270 mm 2 x 12,5 mm gypsum 1 x 12 mm plywood 95 mm C-profiles Gap between c- profiles (min. 6 mm) 95 mm C-profiles 1 x 12 mm plywood 2 x 12,5 mm gypsum	AR-014170	no	Gypsum wall including metal studs etc. Built as double wall due to acoustic demand	> Rw 55dB	Gypsum wall including metal studs etc. Built as double wall due to acoustic demand, including the embedded steel substructure.	Painted on interior side/inside control room. NCS S-8000-N Skirting: Wooden skirting, 15x56 mm NCS S-8000-N		
	Sound lock walls	AW17	Kvadrat Softcell Acoustical panels Thickness 55 mm Textile on alufaming magnetic bracket, mounted on gypsum wall behind Finish: Firetreated to Fire Class C acc. ASTM, 100% transparent Sound absorbtion Class A	AR-015520	yes	Kvadrat acoustics, soft cell	Absorption Class A (min. Aw = 0,9)	fabric panels tensioned on aluminium frames covering the embedded absorber .	Remix 3 0452 Skirting: Wooden skirting, 15x56 mm NCS S-3005-Y20R		kvadrat@kvadrat.org
	Proscenium Front Lyric Theatre	AW40A	ASH WOOD VENEER 0,7MM BIRCH PLYWOOD 2 X 18MM FINISH: FIRE TREATED TO FIRE CLASS C ACC. ASTM E84, 100% TRANSPARENT VARNISH, ULTRA MATTE, GLOSS 2	AR-014191 to AR-014294	yes	Ash wood veneer	30 kg m2	ALL LAYERS MUST BE BONDED TO THE STRUCTURE TIGHTLY AND CONTINUOUSLY INTO ONE SOLID MONOLITHIC BODY, WITH 0 AIR GAPS OR BUBBLES BETWEEN LAYERS. THE RESULTING COMPLEX SHOULD ACHIEVE A SURFACE DENSITY OF MIN 30KG/M2. THE MINIMUM WEIGHTS PER UNIT AREA SHOULD BE ACHIEVED AT ALL POINTS ON THE SURFACES.			
	Stage Front	AW41	BIRCH PLYWOOD 22MM WOOD STAIN APPLIED OILED BLACK MATT IN 2 LAYERS ON BOTH SIDES	AR-014191 to AR-014294	yes	Birch Plywood			WOOD STAIN APPLIED OILED BLACK MATT IN 2 LAYERS ON BOTH SIDES		
	Orchestra Pit Wall. Fixed. Lyric Theatre	AW42A	ASH WOOD VENEER 0,7MM BIRCH PLYWOOD 2X12MM FINISH: FIRE TREATED TO FIRE CLASS C ACC. ASTM E84, 100% TRANSPARENT VARNISH, ULTRA MATTE, GLOSS 2	AR-014191 to AR-014294	yes	Ash Wood veneer			FINISH: FIRE TREATED TO FIRE CLASS C ACC. ASTM E84, 100% TRANSPARENT VARNISH, ULTRA MATTE, GLOSS 2		
	Orchestra Pit Wall. Removeable. Lyric Theatre	AW43A	ASH WOOD VENEER 0,7MM BIRCH PLYWOOD 2X12MM FINISH: FIRE TREATED TO FIRE CLASS C ACC. ASTM E84, 100% TRANSPARENT VARNISH, ULTRA MATTE, GLOSS 2	AR-014191 to AR-014294	yes	Ash Wood veneer			FINISH: FIRE TREATED TO FIRE CLASS C ACC. ASTM E84, 100% TRANSPARENT VARNISH, ULTRA MATTE, GLOSS 2		
	Sound Mix Wagon Wall. Lyric Theatre	AW44A	ASH WOOD VENEER 0,7MM BIRCH PLYWOOD 2X12MM FINISH: FIRE TREATED TO FIRE CLASS C ACC. ASTM E84, 100% TRANSPARENT VARNISH, ULTRA MATTE, GLOSS 2	AR-014191 to AR-014294	yes	Ash Wood veneer			FINISH: FIRE TREATED TO FIRE CLASS C ACC. ASTM E84, 100% TRANSPARENT VARNISH, ULTRA MATTE, GLOSS 2		
BALCONY FRONT	balcony fronts	AW18	FRONT: SOLID WOOD, ASH THICKNESS: 155 MM CNC CUT TEXTURE / OPENINGS ACC. TO 3D MODEL L- PROFILES, MOUNTED ON SUBSTRUCTURE FOR BALCONY STEEL SUBSTRUCTURE TO BE CALCULATED BY CONTRACTOR, MOUNTED ON MAIN STEEL STRUCTURE BY BH. MIN. 30 KG/M2 FOR TOTAL BUILD-UP FINISH: FIRE TREATED TO FIRE CLASS C ACC. ASTM E84, 100% TRANSPARENT VARNISH, ULTRAMATTE, GLOSS 2 VISIBLE BACK (SEAT SIDE): ASH VENEER ON BIRCH PLYWOOD THICKNESS 18MM PLYWOOD WITH VENEER 25 MM HATPROFILES, SPACERS FINISH: FIRE TREATED TO FIRE CLASS C ACC. ASTM E84, 100% TRANSPARENT VARNISH, ULTRAMATTE, GLOSS 2	AR-015570 - AR-015573	yes	Ash wood. Solid. Mounted on steel structure according to contractor	min 30 kg / m2	Min depth 55 mm solid wood CNC cut Texture / Openings acc. To 3D model Any deviation from the design affecting opening ratio, size or distribution of solid elements to be submitted to acoustician fore review and aproval All layers must be bonded to the structure tightly and continuously into one solid monolithic body, with 0 air gaps or bubbles between layers. The resulting complex should achieve a surface density of min 30kg/m2. The minimum weights per unit area should be achieved at all points on the surfaces. For textured surfaces, this means the minimum should be met at the deepest depressions, where material (or assembly) is the thinnest.	Fire retardant treated to class C, 100 % transparent Varnish, ultra matte, gloss 2		JJI Inventar JJi Akustik & Inventar A/S info@jji.as +45 4483 0208 Baltorpbakken 5 DK-2750 Ballerup https://www.jji.as/in-sign-akustik Contact person: Janna Linn Grunth < jlg@jji.as >
	Balcony Front Guard Rail	RL32	Steel Railing 50x15 mm handrail, powdercoated, ncs8500N Balustres 50x15 mm, powdercoated, ncs8500N Fixed on steel substructure for balcony fronts	AR-015570 - AR-015573	yes	Steel plate		15mm deep 50 mm wide,	black painted ncs8500N		
	Back of balcony fronts	See AW18		AR-015570 - AR-015573	yes	Birch plywood panels or gypsum core. Ash wood veneer	N/R - cavity filled with mineral wool		Fire retardant treated to class C, 100 % transparent Varnish, ultra matte, gloss 2		JJI Inventar JJi Akustik & Inventar A/S info@jji.as +45 4483 0208 Baltorpbakken 5 DK-2750 Ballerup https://www.jji.as/in-sign-akustik Contact person: Janna Linn Grunth < jlg@jji.as >
FLOORS	stalls floor	F23A	Wood Flooring on stalls LYRIC THEATRE FLOOR (70KG/M2): 20 MM ASH WOOD PLANKS 16X65X300-600 MM, 16 MM ADHESIVE 4 MM EXTRA 30MM CONCRETE IF MACHINERY CANNOT ACHIEVE WEIGHT THE MACHINERY BELOW, ACCORDING TO INFORMATION FROM CONSULTANTS AND PRODUCERS	AR-015521	yes	Ash Wood mounted on theatre equipement	Min. surface density requirement of 70kg/m2 - to be met by the total build-up (finish + underlay) with no void.	ash parket Ash woodfloor 65mm wide planks, 16 mm thick. Color/Treatment: Matte Lacquered, All edges to be finished with 20mm solid ash plank All layers must be bonded to the structure tightly and continuously into one solid monolithic body, with no air gaps or bubbles between layers. The min. 70kg/m2 mass must be met by the resulting complex.	Ultra matt lacquer		Hørning Parket A/S Christiansmindevej 12 DK-8660 Skanderborg +45 7027 6600 sales@horningfloor.dk https://www.horningfloor.dk/?lang=en Contact person: Jacob Schedler js@horningfloor.dk

Issued for Construction - Lyric Theatre - Material Schedule

0. All Interior finishes shall comply with Table 803.3, SBC 801
1. All reference manufacturers, brands and products are representative of the design intent as referenced in the design drawings, specifications, schedules and reports. They may be substituted under a Contractor's Proposal provided that they are accepted by the
2. All divergence from the reference products/ materials are to be formally notified in writing to the designer. The Designer shall have not less than 10 working days to respond to all proposals. The Designer reserves the right to reject the proposed alternative
3. All suggested alternative samples are to be issued to the Designer for review at least 10 working days prior to the submission of a formal Contractor's Proposal. Acceptance of the sample by the Designer does not relieve the Contractor of conformance of the installation
4. Image swatches are indicative only and are not to be used for colour matching, sampling, or benchmarking.
5. Refer to the design drawings for locations of finishes.



Date





Rev.Date
Rev. No.



31.1.2024

31.1.2024
FOO

LYRIC THEATRE - Material Schedule

TYPE	NAME	RVT	DRAWING	visible	material	density / acoustic requirement	description	treatment/color	picture	contact	
	balcony floor	F22A	Wood Flooring on CLT LYRIC THEATRE BALCONY FLOOR (70KG/M2): 150 MM ASH WOOD PLANKS 20X65X300-600 MM, ADHESIVE 10 MM CLT (55KG/M2), 120MM STRUCTURE (MAX 100MM), SEE DRAWINGS FROM STRUCTURE FOR DETAILS	AR-015570 - AR-015573	yes	Ash Wood mounted on CLT slab	Min. surface density requirement of 70kg/m2 - to be met by the total build-up (finish + underlay) with no void.	ash parket Ash woodfloor 65mm wide planks, 20 mm thick. Color/Treatment: Matte Lacquered, All edges to be finished with 16mm solid ash plank All layers must be bonded to the structure tightly and continuously into one solid monolithic body, with no air gaps or bubbles between layers. The min. 70kg/m2 mass must be met by the resulting complex.		Hørning Parket A/S Christiansmindevej 12 DK-8660 Skanderborg +45 7027 6600 sales@horningfloor.dk https://www.horningfloor.dk/?lang=en Contact person: Jacob Schedler js@horningfloor.dk	
	sound locks	F03B	Carpet flooring SOUND ABSORBENT CARPET: 150 MM SOUND ABSORBENT CARPET 10 MM ADHESIVE AND LEVELLING 10 MM LIGHTWEIGHT SCREED, 75 MM LIGHTWEIGHT VOID FORMER, 55 MM	AR-015540	yes	carpet floor Tufted carpet, 100% polyamide ultra soft AS Van besouw 2609-050 synthetisch, 10 mm thickness 1666 g/m2 or acceptable equivalent	Tufted Desity requirement	Sound absorbent Carpet, 10 mm Adhesive and levelling, 10 mm Screed, 130 mm		https://besouw.nl/en/	
	control room floor	F06A	Raised floor, Antistatic RAISED FLOOR CARPET ANTI-STATIC DIMENSION TO UNDERFLOOR 1250 OR 950 MM CARPET ANTISTATIC (600X600 MM), COLOUR BLACK, 5 MM RAISED FLOOR, LOAD CAPACITY 500 N/M² ACCESS PLATES AND LOCATION OF CABLE TRAYS ACC. TO ROOM DRAWING	AR-014170	yes/no	raised floor tiles with Carpet as Epoca Knit Charcoal, 085679548 or acceptable equivalent	antistatic finish 500 daN/m² capacity Accessible due to installations (e.g. cable trays below)	Carpet tiles on raised floor			
	Orchestra Pit	F24A	Wood Flooring, Painted Black F24A ORCHESTRA PIT FLOOR 200MM DECKING 45MM 8MM HARDWOOD (ACCORDING TO THEATHER CONSULTANT) 29MM SOFTWOOD CORE (ACCORDING TO ACOUSTICS SPECS) 8MM HARDWOOD (ACCORDING TO THEATHER CONSULTANT) 45X45MM SOFTWOOD SLEEPERS C/C300MM 90X90MM SOFTWOOD BEAMS C/C 900MM 20MM AIR VOID / JOIST LEVELERS VAPOUR BARRIER	AR-015521	yes/no		See: Nagata, Appendix D Construction Requirements and Recommendations Room Acoustics, Performance Spaces	All Cable racks, access hatches or visible equipment supported on lighting galleries should be painted black .	Color: RAL TBD (ABU)		
	Sound Mix Floor Finish	F27A	ASH WOOD PLANKS 16X65X300-600 MM, 16 MM ADHESIVE 4 MM	AR-014194	yes	Ash Wood mounted on theatre equipment	Min. surface density requirement of 70kg/m2 - to be met by the total build-up (finish + underlay) with no void.	All layers must be bonded to the structure tightly and continuously into one solid monolithic body, with no air gaps or bubbles between layers. The min. 70kg/m2 mass must be met by the resulting complex.	Ultra matt lacquer		Hørning Parket A/S Christiansmindevej 12 DK-8660 Skanderborg +45 7027 6600 sales@horningfloor.dk https://www.horningfloor.dk/?lang=en Contact person: Jacob Schedler js@horningfloor.dk
CEILINGS	soffits	SC52	Balcony soffits: Ash veneer on Birch plywood ASH VENEER PANEL ON BIRCH PLYWOOD (LT) TOTAL BUILD-UP: 125 MM STEEL SUBSTRUCTURE TO BE CALCULATED BY CONTRACTOR C-PROFILES 70 MM MOUNTED ON SUBSTRUCTURE FOR CLT/BALCONY 25 MM HATPROFILES 3 LAYERS OF GYPSUM, WHERE CURVED / STRAIGHT PLYWOOD WITH VENEER - 12+6 MM MIN. 30 KG/M2 FOR TOTAL BUILD-UP FINISH: FIRE TREATED TO FIRE CLASS C ACC. ASTM E84, 100% TRANSPARENT VARNISH, ULTRAMATTE, GLOSS 2	AR-015570 - AR-015573	yes	Ash wood veneer	min 30 kg / m2	ash wood veneer mounted on gypsum board veneer slicing : crown cut veneer mixing: mix. reverse slip matched. varying number of flitches per panel with one order : 3 to 6 All layers must be bonded to the structure tightly and continuously into one solid monolithic body, with no air gaps or bubbles between layers. The resulting complex should achieve a surface density of min 30kg/m2	Fire retardant treated to class C, 100 % transparent Varnish, ultra matte, gloss 2 Fire Class to be tested for this project. Treatment: 2 times lacquer type AB19. Clear lacquer, gloss 5 1 time finish lacquer, clear, ultramatte, gloss 2.		JJI inventar JJi Akustik & Inventar A/S info@jji.as +45 4483 0208 Baltorpbakken 5 DK-2750 Ballerup https://www.jji.as/in-sign-akustik Contact person: Janna Linn Grunth <jlg@jji.as>
	Transonare Hatches for speaker boxes	2D only		AR-015571	yes	Gerriets fabric Skylight 350 - 3071, mounted in Kvadrat Softcell frames or acceptable equivalent		Kvadrat Softcell frames with hinge / magnatic push latch	Skylight 350 - 3071, Gerriets Fire retardant treated to class C acc. ASTM E84		Gerriets
	Access hatches in soffit	2D only		AR-015540	yes	Ash wood veneer on hatch Frame powdercoated NCS 8500-N		Knauf Acces Hatch or acceptable equivalent, behind SC52 demountable panel acc. To drawing Access to EL cabletrays. Embedded "invisible" hatch with same finish as the surrounding ceiling	Fire retardant treated to class C, 100 % transparent Varnish, ultra matte, gloss 2 Treatment: 2 times lacquer type AB19. Clear lacquer, gloss 5 1 time finish lacquer, clear, ultramatte, gloss 2.		Knauf acces hatch with demountable panel
	acoustic ceiling	SC72	Acoustic Ceiling, Solid GRC SOLID PRECAST FIBRE CEMENT PANELS (GRC), DOUBLE CURVED (LT) THICKNESS TO ACHIEVE SURFACE WEIGHT MIN 60KG/M2 TOTAL BUILD-UP: MIN. 120 MM ELEMENTS WITH TONGUE AND GROOVE CONNECTIONS MOUNTED ON STEEL SUBSTRUCTURE TO BE CALCULATED BY CONTRACTOR	AR-015101 AR-014150	no	fibre cement panels, precast, curved / double curved	min. 60kg/m2	Fiber concrete elements mounted on steel frame construction according to contractor - Geometry to follow drawing.....	Fire Class C acc. ASTM E84 Color: Grey, RAL 7023, BBF No. 96-S		https://www.bbfiberbeton.dk/

Issued for Construction - Lyric Theatre - Material Schedule

0. All Interior finishes shall comply with Table 803.3, SBC 801
1. All reference manufacturers, brands and products are representative of the design intent as referenced in the design drawings, specifications, schedules and reports. They may be substituted under a Contractor's Proposal provided that they are accepted by the
2. All divergence from the reference products/ materials are to be formally notified in writing to the designer. The Designer shall have not less than 10 working days to respond to all proposals. The Designer reserves the right to reject the proposed alternative
3. All suggested alternative samples are to be issued to the Designer for review at least 10 working days prior to the submission of a formal Contractor's Proposal. Acceptance of the sample by the Designer does not relieve the Contractor of conformance of the installation
4. Image swatches are indicative only and are not to be used for colour matching, sampling, or benchmarking.
5. Refer to the design drawings for locations of finishes.



Date

Rev.Date
Rev. No.



31.1.2024

31.1.2024
FOO

LYRIC THEATRE - Material Schedule

TYPE	NAME	RVT	DRAWING	visible	material	density / acoustic requirement	description	treatment/color	picture	contact
	architectural ceiling	SC51	Architectural Ceiling (Transparent) ASH WOOD BARS, TRANSPARENT (LT) TOTAL BUILD-UP: 149 MM FRAMES MOUNTED ON BEND STEEL PROFILES ACC. TO CONTRACTOR BEND STEEL FRAME ACC. TO CONTRACTOR ASH WOOD - 12,5 MM, GAP: 12,5 MM SPACING: 25 MM XX TO CENTER SLAT MIN 50% OPEN FIRE CLASS C ACC. ASTM E84	AR-015520	yes	Ash Wood, 12,5 mm x 10 mm, Spacing 12,5 mm Mounted on bend steelframe acc. To contractor Frames mounted on bend steel profiles acc. To contactor	Acoustically transparent, curved ceiling of small wooden lamellas, evenly spaced, on metal frames. Mounted on curved structure. Any deviation from the design affecting opening ratio, size or distribution of solid elements to be submitted to acoustician for review and approval all elements to be fixed tightly and contacts to be treated with soft non-porous material to prevent rattling and vibrations	Fire Class C acc. ASTM E84		JJI Inventar JJi Akustik & Inventar A/S info@jji.as +45 4483 0208 Baltorpbakken 5 DK-2750 Ballerup https://www.jji.as/in-sign-akustik Contact person: Janna Linn Grunth <jlg@jji.as>
	sound locks	SC42	Kvadrat Softcell Acoustical ceiling panels ACOUSTIC SOFT CELL (LT) TOTAL BUILD-UP: 55 MM FIXING DEVICE - 6 MM FABRIC TENSIONED ON ALUMINUM FRAME WITH ABSORPTIVE MATERIAL INTEGRATED - 49MM SOUND ABSORPTION CLASS: CLASS A FIRE: CLASS B	AR-015520	yes	Kvadrat acoustics, soft cell or acceptable equivalent	Sound Absorption Class A (min. Aw = 0,9) fabric panels tensioned on aluminiumframes covering the absorber embedded.	kvadrat ginger 2 0122 Fire Class C acc. ASTM E84		Kvadrat acoustic Kvadrat A/S Pakhus 48 Klubiensvej 22, Frihavnen 2150 Nordhavn, Denmark https://www.kvadrat.dk/en/kvadrat-acoustics Contact person: Jesper Vangby Country Director M +45 3080 2216
	lighting gallery and forestage				yes/no	Grating on steel structure	All Cable racks, access hatches or visible equipment supported on lighting galleries should be painted black .	Color: NCS 8500-N		
	Orchestra Pit - soffit	SC54	Orchestra Pit Soffit, Painted Black PLYWOOD PAINTED BLACK TOTAL BUILD-UP: 100 MM 45X70MM C PROFILES C/C MAC 450MM 15MM PLYWOOD 15MM PLYWOOD PAINTED BLACK WEIGHT MIN 15KG/M2	AR-015521	yes		min. 15kg/m2 All layers must be bonded to the structure tightly and continuously into one solid monolithic body, with no air gaps or bubbles between layers. The resulting complex should achieve a surface density of min 15kg/m2	Color: NCS 8500-N Fire Class C acc. ASTM E84		
	Control Room Ceiling	SC11b	System Ceiling with seamless edges, 600x600 mm Build-up: 60 mm Main runner and cross tees - 38 mm Hidden Clip-in system Stone wool tiles 600x600 mm - 22 mm	AR-014170	yes	System ceiling Main runner and cross tees - 38 mm Hidden Clip-in system Stone wool tiles 600x600 mm - 22 mm	Acoustics: Aw 0.95 (class A) Main runner and cross tees - 38 mm Hidden Clip-in system Stone wool tiles 600x600 mm - 22 mm Fire: A1 Demountable for access Humidity class 1/C/ON	NCS S-8000-N		
	Control room Gypsum Ceiling	SC45	Gypsum Ceiling, Min. Rw 55dB Thickness 170 mm 2 x 12,5 mm gypsum 1 x 12 mm plywood 95 mm C-profiles / Steel structure RHS 90x90 1 x 12 mm plywood 2 x 12,5 mm gypsum	AR-014170	no	Gypsum ceiling including metal studs etc.	> Rw 55dB Gypsum ceiling	NCS S-8000-N		
DOORS	Soundlocks to Halls				yes	In general see door schedule	In general see door schedule > Rw 40dB	In general see door schedule Veneer surface on doors to be compliant with door supplier warranty. Veneer surfaces to be coordinated and matched to adjacent veneered walls / solid walls		JJI Inventar JJi Akustik & Inventar A/S info@jji.as +45 4483 0208 Baltorpbakken 5 DK-2750 Ballerup https://www.jji.as/in-sign-akustik Contact person: Janna Linn Grunth <jlg@jji.as>
	Foyer to soundlocks				yes	In general see door schedule	In general see door schedule > Rw 40dB	In general see door schedule Veneer surface on doors to be compliant with door supplier warranty. Veneer surfaces to be coordinated and matched to adjacent veneered walls / solid walls		JJI Inventar JJi Akustik & Inventar A/S info@jji.as +45 4483 0208 Baltorpbakken 5 DK-2750 Ballerup https://www.jji.as/in-sign-akustik Contact person: Janna Linn Grunth <jlg@jji.as>
	Curtain doors	AW19	ACOUSTIC WALL, SOLID WOOD, ASH THICKNESS MIN. 55 MM MOUNTED ON STEEL SUBSTRUCTURE TO BE CALCULATED BY CONTRACTOR EMBEDDED CURTAIN DOORS WITH CONCEALED HINGES DENSITY MIN. 30 KG/M2 FOR TOTAL BUILD-UP FINISH: FIRETREATED TO FIRE CLASS C ACC. ASTM E84, 100% TRANSPARENT VARNISH, ULTRAMATTE, GLOSS 2	AR-015500 and AR-015501	yes	solid ash wood as AW19	+MIN. 30 KG/M² solid ash wood doors with concealed hinges and interconnecting locks (due to height)	Doors to be compliant with door supplier warranty. Surface to be coordinated and matched to adjacent solid walls		JJI Inventar JJi Akustik & Inventar A/S info@jji.as +45 4483 0208 Baltorpbakken 5 DK-2750 Ballerup https://www.jji.as/in-sign-akustik Contact person: Janna Linn Grunth <jlg@jji.as>
OTHERS	Control room window			AR-014170	yes	Refer to drawing no. JOH-HLA-S4-01-056-005-00-DR-AR-014170	Angled 6 dg. Upwards min. Rw 45 dB Ultraclear glass as SGG VISION-LITE STADIP PROTECT with low-reflective coating on both sides.	low-reflective coating on both sides.		Saint Gobain

Issued for Construction - Lyric Theatre - Material Schedule

0. All Interior finishes shall comply with Table 803.3, SBC 801
1. All reference manufacturers, brands and products are representative of the design intent as referenced in the design drawings, specifications, schedules and reports. They may be substituted under a Contractor's Proposal provided that they are accepted by the
2. All divergence from the reference products/ materials are to be formally notified in writing to the designer. The Designer shall have not less than 10 working days to respond to all proposals. The Designer reserves the right to reject the proposed alternative
3. All suggested alternative samples are to be issued to the Designer for review at least 10 working days prior to the submission of a formal Contractor's Proposal. Acceptance of the sample by the Designer does not relieve the Contractor of conformance of the installation
4. Image swatches are indicative only and are not to be used for colour matching, sampling, or benchmarking.
5. Refer to the design drawings for locations of finishes.



Date


Rev.Date
Rev. No.



31.1.2024

31.1.2024
FOO

LYRIC THEATRE - Material Schedule

TYPE	NAME	RVT	DRAWING	visible	material	density / acoustic requirement	description	treatment/color	picture	contact
	Steps, step sides, Nosing			yes	Ash Wood mounted on CLT slab / woodem stud build-up	Min. surface density requirement of 70kg/m2 fulfilled under steps	Ash woodfloor 65 wide planks, 20 mm thick. Color/Treatment: Matte Lacquered, All edges to be finished with 20mm solid ash plank, toned for contrast			
	Plenum Box	PW01	Back: Plenum box build-up Airtightness requirement of 0.8/s.m2 @ 50Pa in relation to the floor area of the plenum 12 mm Plywood Vapourbarrier 12.5 mm Gypsum 25 mm hatprofiles, C.profiles 40/70/95 mm depended on position	AR-015570-73 (not Keynoted)	no	Plenum box build-up 12 mm Plywood Vapourbarrier 12.5 mm Gypsum	Airtightness requirement of 0.8/s.m2 @ 50Pa in relation to the floor area of the plenum.	Build-up of studs + plywood, 12 mm + vapour membrane + 12.5 gypsum.	N/R	
	Acoustic curtain along the auditorium wall under curtain track	-		yes	Textile	min. Density 0,5 kg/m2 of drapery 100% fullness (total min density 1kg/m 2)	Fabric to be tested acc. To ISO 354:2003	Alicante Color to match Gerriets Alicante Light beig		Gerriets or acceptable equivalent
	Curtain of acoustics banners	-		yes	Textile	min. Density 0,5 kg/m2 of drapery 2 layers, flat (total min density 1kg/m²)	Fabric and banner to be tested acc. To ISO 354:2003	Abrosber CS Color: Dark Grey		Gerriets or acceptable equivalent
	LYRIC THEATRE GUARD RAIL	RL30	LYRIC THEATRE GUARD RAIL WELDED STEEL RAILING. FLAT STEEL TOP AND BOTTOM BAR 30X6MM. CIRCULAR BALUSTRADES Ø10MM SPACED 100MM. PAINTED NCS8500-N. BOLTED TO THE FLOOR WUTH COUNTERSUNK SCREWS	AR-015430	yes	6x30 mm flat steel frame, welded	N/R	FLAT STEEL TOP AND BOTTOM BAR 30X6MM. CIRCULAR BALUSTRADES Ø10MM SPACED 100MM. PAINTED NCS8500-N. BOLTED TO THE FLOOR WITH COUNTERSUNK SCREWS	Painted, NCS 8500-N	
	LYRIC THEATRE LOOP RAILS	RL31	LYRIC THEATRE LOOP RAILS WELDED 30X6MM FLAT STEEL BAR. PAINTED NCS8500-N . BOLTED TO AISLE STAIR SIDE SOLID ASH WOOD TOP. 50*20MM.	AR-015430	yes	6x30 mm flat steel frame, welded	N/R	FLAT STEEL BAR. PAINTED NCS8500-N . BOLTED TO AISLE STAIR SIDE SOLID ASH WOOD TOP. 50*20MM.	Painted, NCS 8500-N	
	LYRIC THEATRE BALCONY FRONT RAIL	RL32	LYRIC THEATRE BALCONY FRONT RAIL WELDED 30X6MM FLAT STEEL BAR. PAINTED NCS8500-N REFER TO BALCONY FRONT DETAILS	AR-014150 AR-015430	yes	6x30 mm flat steel frame, welded	N/R	FLAT STEEL BAR. PAINTED NCS8500-N REFER TO BALCONY FRONT DETAILS	Painted, NCS 8500-N	
OTHER	LYRIC THEATRE ORCHESTRA SHELL			yes		Overhead reflectors: min surface mass 30kg/m2 Walls, shelf: min surface mass 15kg/m2				

Issued for Construction - Mid Scale Theatre - Material Schedule

0. All Interior finishes shall comply with Table 803.3, SBC 801
1. All reference manufacturers, brands and products are representative of the design intent as referenced in the design drawings, specifications, schedules and reports. They may be substituted under a Contractor's Proposal provided that they are accepted by the Designers and that they conform to any specified performance requirements.
2. All divergence from the reference products/ materials are to be formally notified in writing to the designer. The Designer shall have not less than 10 working days to respond to all proposals. The Designer reserves the right to reject the proposed alternative product or material.
3. All suggested alternative samples are to be issued to the Designer for review at least 10 working days prior to the submission of a formal Contractor's Proposal. Acceptance of the sample by the Designer does not relieve the Contractor of conformance of the installation works to the Design Intent.
4. Image swatches are indicative only and are not to be used for colour matching, sampling, or benchmarking.
5. Refer to the design drawings for locations of finishes.

Date	31.1.2024
Rev.Date	31.1.2024
Rev. No.	FOO

MID-SCALE THEATRE - Material Schedule

TYPE	NAME	RVT	DRAWING	visible	material	density / acoustic requirement	description	treatment/color	picture	contact
WALLS	Back Walls - Acoustic Transparent	AW20	Acoustic Wall, Black Lacquered Solid wood, Ash 30mm solid ash acoustically transparent wall min 60% open 70x65x5mm Horizontal U-profile blued steel C/C 600mm - C/C 1200mm 79mm panel mounting bracket 41mm Halfen profile H2M 41x41mm 50x50mm RHS profile max C/C 1000m (To be verified by contractor)	AR-015600 AR-014230 AR-015004	yes	Black stained ash wood. Solid.	Acoustically transparent with min. 60% openess. Any deviation from the design affecting opening ratio, size or distribution of solid elements to be submitted to acoustician fore review and aproval	min. 60% open for acoustic transparency. Composition of solid elements per architectural intention. Wall consists of panel elements that are produced of 13x30mm solid ash pieces. These solid ash pieces are cut to form triangles in vertical direction. The horizontal parts are 2x13mm solid ash pieces. The smallest production element is a row of triangles that is glued and fixed with 2 nails per connection point to a 13mm horizontal piece on top and bottom.	Black stain, Fire retardant treated to class C acc. ASTM, 100 % transparent Varnish, ultra matte, gloss 2	JJI inventar JJi Akustik & Inventar A/S info@jji.as +45 4483 0208 Baltorpbakken 5 DK- 2750 Ballerup https://www.jji.as/in-sign-akustik Contact person: Janna Linn Grunth <jlg@jji.as>
	Back Walls - Acoustic (behind acoustic transparent)	AW12A AW12B AW12C	Acoustic Wall, Solid GRC Behind acoustically transparent wall Thickness min. 15 mm (min. 30kg/m2) Elements with tongue and groove connections Mounted on steel substructure to be calculated by contractor Type A: ZigZag shape with var. Angles acc. To position Type B: Bubble shape vertical wall Type C: Big Bubble shape	AR-015602 AR-015004	no/yes	Fiber Cement	min 30kg/m2	Glassfiber reinforced concrete elements (GRC) mounted on steel frame construction according to contractor . Geometry to follow drawing.	Black painted RAL 9005	BB Fiberbeton / Fiber concrete www.bbfiberbeton.dk/en https://www.bbfiberbeton.dk/en/contact Contact person: Helene Bieger helene@bbfiberbeton.dk
	Back Walls - Acoustic (behind acoustic transparent)	BW33 BW34 BW35 BW36 BW37 BW38	Blockwork Variable Thicknes 200-260mm- relate to plan drawings Fire rating 4 hours min. 64 dB Rw without plaster plaster 10mm	AR-015001 015030	AR-no/yes	Blockwork	min 30 kg / m2		render, painted black RAL 9005	
	Horizontal U Profiles	AW20	Horizontal division of solid ash wall panels. Part of AW20	AR-015600 AR-014230	yes	Blued steel profile		70x65x5mm custom steel profile, 2mm inside corner bend radius. Fastened to Halfen profile.	Blued steel	
	Orchestra Pit Wall	AW29A	Blacked Lacquered Ash Veneer ash veneered acoustic wall 80mm seating side 12mm+1mm veneered black ash plywood 4mm plywood/hidden mounting connection for last layer 3x12.5mm gypsum boards min 30kg/m2 25mm hatprofile	AR-015004 AR-014230	yes	plywood, black lacquered ash wood veneer	All layers must be bonded to the structure tightly and continuously into one solid monolithic body, with no air gaps or bubbles between layers. The resulting complex should achieve a surface density of min 30kg/m2	Plywood with surface ash veneer, 13mm, hidden mounted. Panel division acc. to floor plan. Hidden mounting profiles and 4mm plywood panel, 12mm plywood, airtight memmbrane, 2x12,5mm gypsum, 25 mm hatprofiles	Black stained, fire retardant treated to class C acc. ASTM, 100 % transparent, ultra matte, gloss 2. Veneer requirements same as soffit.	JJI inventar JJi Akustik & Inventar A/S
	Lighting Position Walls	AW29B	Blacked Lacquered Ash Veneer ash veneered acoustic wall 125mm seating side 12mm +1mm veneered black ash plywood 4mm plywood/hidden mounting connection for last layer 3x12.5mm gypsum boards min 30kg/m2 70mm C profile C/C 300mm	AR-015004 AR-014201	yes	plywood, black lacquered ash wood veneer	All layers must be bonded to the structure tightly and continuously into one solid monolithic body, with no air gaps or bubbles between layers. The resulting complex should achieve a surface density of min 30kg/m2	Plywood with surface ash veneer, 13mm, hidden mounted. Panel division acc. to floor plan. Hidden mounting profiles and 4mm plywood panel, 12mm plywood, airtight memmbrane, 2x12,5mm gypsum, 70 mm C Profile c/c300mm	Black stained, fire retardant treated to class C acc. ASTM, 100 % transparent, ultra matte, gloss 2. Veneer requirements same as soffit.	JJI inventar JJi Akustik & Inventar A/S
	Risers in balcony - behind seating	AW29C	Blacked Lacquered Ash Veneer ash veneered acoustic wall 80mm seating side 12mm+1mm veneered black ash plywood 4mm plywood/hidden mounting connection For last layer: 3x12.5mm gypsum boards min 30KG/m2 with airtight membrabe 25mm hatprofile	AR-015670 AR-015671 AR-015004	yes	plywood, black lacquered ash wood veneer	All layers must be bonded to the structure tightly and continuously into one solid monolithic body, with no air gaps or bubbles between layers. The resulting complex should achieve a surface density of min 30kg/m2	Plywood with surface ash veneer, 13mm, hidden mounted. Panel division acc. to floor plan. Hidden mounting profiles and 4mm plywood panel, 12mm plywood, airtight memmbrane, 2x12,5mm gypsum, 25 mm hatprofiles	Black stained, fire retardant treated to class C acc. ASTM, 100 % transparent, ultra matte, gloss 2. Veneer requirements same as soffit.	JJI inventar JJi Akustik & Inventar A/S
	Other Walls - Partition Walls / VIP area /Balcony Railing	AW28	Front: Blacked Lacquered Ash veneer 1+12mm veneer black ash plywood 12mm plywood 50mm RHS for curved parts rolled to radius 50mm Minaral wool 12mm plywood 1mm+12mm veneered black ash plywood	AR-015670 AR-015671 AR-015004	yes	plywood, black lacquered ash wood veneer		Plywood with surface ash veneer, 13mm, hidden mounted. Hidden mounting profiles and 4mm plywood panel, 12mm plywood 50mm RHS for curved parts rolled to radius 12mm plywood 1mm+12mm veneered black ash plywood	black stained, fire retardant treated to class C, 100 % transparent Varnish, ultra matte, gloss 2 Veneer requirements same as soffit.	JJI inventar JJi Akustik & Inventar A/S
	Other Walls - Control Room/Back Wall	IW46	Internal Wall Cladding TYPE 46 Thickness 96mm 21mm perforated plywood, mounted with black screws Painted Black Holed Diameter 5mm spacing: 16mm align (x/y) 50mm acoustic insulation 25mm aluminium hat profiles, 300mm C/C	AR-015006	yes	perforated plywood	>Rw 50dB	21mm perforated plywood, mounted with black screws Painted Black Holed Diameter 5mm spacing: 16mm align (x/y) 50mm acoustic insulation 25mm aluminium hat profiles, 300mm C/C	RAL9005.	
	Other Walls - Control Room/Towards Hall	AW23	Control Room Wall 2x12.5mm gypsumboard 1x12mm plywood 38mm L bracket with 20mm insulation 200x100mm RHS main structure (2x95mm mineral wool) variable outer part to make acoustic shape min 38mm L bracket with 20mm insulation 3x12.5 gypsumboard, (min 30kg/m2) last layer painted black hall side	AR-015601 AR-015004	yes	Gypum wall with steel structure	>Rw 50dB All layers must be bonded to the structure tightly and continuously into one solid monolithic body, with no air gaps or bubbles between layers. The resulting complex should achieve a surface density of min 30kg/m2	Due to the long (ca 10m) opening for the control room window this wall needs a strong steel structure, acc to contractor.	RAL9005.	

Issued for Construction - Mid Scale Theatre - Material Schedule

0. All Interior finishes shall comply with Table 803.3, SBC 801
1. All reference manufacturers, brands and products are representative of the design intent as referenced in the design drawings, specifications, schedules and reports. They may be substituted under a Contractor's Proposal provided that they are accepted by the Designers and that they conform to any specified performance requirements.
2. All divergence from the reference products/ materials are to be formally notified in writing to the designer. The Designer shall have not less than 10 working days to respond to all proposals. The Designer reserves the right to reject the proposed alternative product or material.
3. All suggested alternative samples are to be issued to the Designer for review at least 10 working days prior to the submission of a formal Contractor's Proposal. Acceptance of the sample by the Designer does not relieve the Contractor of conformance of the installation works to the Design Intent.
4. Image swatches are indicative only and are not to be used for colour matching, sampling, or benchmarking.
5. Refer to the design drawings for locations of finishes.

Date 31.1.2024

Rev.Date 31.1.2024

Rev. No. F00

MID-SCALE THEATRE - Material Schedule

TYPE	NAME	RVT	DRAWING	visible	material	density / acoustic requirement	description	treatment/color	picture	contact
	Other Walls - Control Room/Towards Hall - Outside Finish	AW20B	Acoustic Wall, Black Lacquered Solid wood, Ash 30mm solid ash acoustically transparent wall min 60% open 70x65x5mm Horizontal U-profile blued steel C/C 600mm - C/C 1200mm 79mm panel mounting bracket 41mm Halfen profile H2M 41x41mm 50x50mm RHS profile max C/C 1000m (integrated) (To be verified by contractor)	AR-015601 AR-015004	yes	Black stained ash wood. Solid.	acoustically transparent with min. 60% openness. Any deviation from the design affecting opening ratio, size or distribution of solid elements to be submitted to acoustician fore review and aproval	min. 60% open for acoustic transparency. Composition of solid elements per architectural intention. Wall consists of panel elements that are produced of 13x30mm solid ash pieces. These solid ash pieces are cut to form triangles in vertical direction. The horizontal parts are 2x13mm solid ash pieces. The smallest production element is a row of triangles that is glued and fixed with 2 nails per connection point to a 13mm horizontal piece on top and bottom.	Black stain, Fire retardant treated to class C acc. ASTM, 100 % transparent Varnish, ultra matte, gloss 2	JJI inventar JJI Akustik & Inventar A/S info@jji.as +45 4483 0208 Baltorpbakken 5 DK- 2750 Ballerup https://www.jji.as/in-sign-akustik Contact person: Janna Linn Grunth <jlg@jji.as>
		AW20C	Acoustic Wall, Black Lacquered Solid wood, Ash 30mm solid ash acoustically transparent wall min 60% open 50mm insulation 20-60kg/m2 black hall side 70x65x5mm Horizontal U-profile blued steel C/C 600mm - C/C 1200mm 79mm panel mounting bracket 41mm Halfen profile H2M 41x41mm 50x50mm RHS profile max C/C 1000m (integrated) (To be verified by contractor)	AR-015601 AR-015004						
	Other Walls - balcony stair side wall	AW27	Ash veneered wall 40mm For Straight parts 1mm + 39mm +1mm Veneered black ash Plywood For curved parts 1mm+12mm Veneered black ash Plywood 6mm Plywood 9mm Plywood 1mm+12mm Veneered black ash Plywood	AR-015004 AR-014202	Yes	Black stained ash wood. Solid.			Black stained, fire retardant treated to class C acc. ASTM, 100 % transparent, ultra matte, gloss 2. Veneer requirements same as soffit.	
	Sound loock walls	AW 25	Sound Lock Walls Metal Clading Wall 80mm 20mm black stainlesssteel hanging metal panels hidden connection 45mm U profiles with hanging brackets 25mm extention brackets 50mm sound insulation cladding fire class-B	AR-015004 015030	AR yes	steel			heat treated steel black colour	
	Proscenium Front Midscale theatre	AW40B	BLACK LACQUERED ASH WOOD VENEER 0,7MM BIRCH PLYWOOD 2 X 18MM FINISH: FIRE TREATED TO FIRE CLASS C ACC. ASTM E84, 100% TRANSPARENT VARNISH, ULTRA MATTE, GLOSS 2	AR-014191 to AR-014294	yes	Black Lacquered Ash wood veneer	30 Kg m2	ALL LAYERS MUST BE BONDED TO THE STRUCTURE TIGHTLY AND CONTINUOUSLY INTO ONE SOLID MONOLITHIC BODY, WITH 0 AIR GAPS OR BUBBLES BETWEEN LAYERS. THE RESULTING COMPLEX SHOULD ACHIEVE A SURFACE DENSITY OF MIN 30KG/M2. THE MINIMUM WEIGHTS PER UNIT AREA SHOULD BE ACHIEVED AT ALL POINTS ON THE SURFACES.		
	Stage Front	AW41	BIRCH PLYWOOD 22MM WOOD STAIN APPLIED OILED BLACK MATT IN 2 LAYERS ON BOTH SIDES	AR-014191 to AR-014294	yes	Birch Plywood				
	Orchestra Pit Wall. Fixed. Midscale theatre	AW42B	BLACK LACQUERED ASH WOOD VENEER 0,7MM BIRCH PLYWOOD 2X12MM FINISH: FIRE TREATED TO FIRE CLASS C ACC. ASTM E84, 100% TRANSPARENT VARNISH, ULTRA MATTE, GLOSS 2	AR-014191 to AR-014294	yes	Black Lacquered Ash wood veneer				
	Orchestra Pit Wall. Removeable. Midscale theatre	AW43B	BLACK LACQUERED ASH WOOD VENEER 0,7MM BIRCH PLYWOOD 2X12MM FINISH: FIRE TREATED TO FIRE CLASS C ACC. ASTM E84, 100% TRANSPARENT VARNISH, ULTRA MATTE, GLOSS 2	AR-014191 to AR-014294	yes	Black Lacquered Ash wood veneer				
	Sound Mix Wagon Wall. Midscale theatre	AW44B	BLACK LACQUERED ASH WOOD VENEER 0,7MM BIRCH PLYWOOD 2X12MM FINISH: FIRE TREATED TO FIRE CLASS C ACC. ASTM E84, 100% TRANSPARENT VARNISH, ULTRA MATTE, GLOSS	AR-014191 to AR-014294	yes	Black Lacquered Ash wood veneer				
BALCONY FRONT	Balcony Front	AW21	Curved Balcony Front with Surface Texture Panel Thickness 200mm 30mm solid ash surface texture panel, curved 6mm plywood, ash veneer lacked black 3x12.5mm gypsum board min 30kg/m2 CA 98mm space for 70x70 RHS Steel structure 12mm plywood 4mm plywood/hidden mounting connection for last layer 12mm+1mm veneered black ash plywood	AR-015670 AR-015671 AR-014533 AR-015004	yes	back side: plywood, black lacquered ash wood veneer front side: Black stained ash wood. Solid.	All layers must be bonded to the structure tightly and continuously into one solid monolithic body, with no air gaps or bubbles between layers. The resulting complex should achieve a surface density of min 30kg/m2	Front as AW20 panels without structure and Halfen profiles. Horizontal parts bent laminated to radius. Backed with 6mm plywood, surface ash veneer, stained black. Fastened to gypsum wall from inside, not visible. Structure: 3x12,5mm gypsum Horizontal 60x40x5mm RHS acc to contractor Vertical 70x70x5mm RHS acc to contractor, fastened to ringbeam 12mm plywood Hidden mounting as Gustafs, 4mm plywood 13mm plywood with oak veneer, stained black, hidden mounted	black stained, fire retardant treated to class C, 100 % transparent Varnish, ultra matte, gloss 2 Veneer requirements same as soffit.	JJI inventar JJI Akustik & Inventar A/S
	Balcony top/bottom edge detail			AR-015670 AR-015671	yes	3mm blued steel plate 25x25x2mm blued steel profile 70x65x5mm blued steel profile		Top: 3mm steel plate, cut to radius, 25x25x2mm lighting channel, U profile, Blued Steel, 70x65x5mm Bottom: U profile, Blued Steel, 70x65x5mm, 3mm steel plate, cut to radius. All elements fastened to balcony structure.	Blued steel	

Issued for Construction - Mid Scale Theatre - Material Schedule

0. All Interior finishes shall comply with Table 803.3, SBC 801
1. All reference manufacturers, brands and products are representative of the design intent as referenced in the design drawings, specifications, schedules and reports. They may be substituted under a Contractor's Proposal provided that they are accepted by the Designers and that they conform to any specified performance requirements.
2. All divergence from the reference products/ materials are to be formally notified in writing to the designer. The Designer shall have not less than 10 working days to respond to all proposals. The Designer reserves the right to reject the proposed alternative product or material.
3. All suggested alternative samples are to be issued to the Designer for review at least 10 working days prior to the submission of a formal Contractor's Proposal. Acceptance of the sample by the Designer does not relieve the Contractor of conformance of the installation works to the Design Intent.
4. Image swatches are indicative only and are not to be used for colour matching, sampling, or benchmarking.
5. Refer to the design drawings for locations of finishes.

Date 31.1.2024

Rev.Date 31.1.2024

Rev. No. F00

MID-SCALE THEATRE - Material Schedule

TYPE	NAME	RVT	DRAWING	visible	material	density / acoustic requirement	description	treatment/color	picture	contact
FLOORS	Balcony	F22B	Wood Flooring on CLT solid smoked oak parquet, charcoal oil 20x63x800-1200mm adhesive/membrane and levelling 10mm 120mm CLT	AR-014223-224 AR-015640 AR-015641 AR-015200	yes	Smoaked Oak solid wood floor, long block, 10mm glue(levelling layer, mounted on CLT.	All layers must be bonded to the structure tightly and continuously into one solid monolithic body, with no air gaps or bubbles between layers. The resulting complex should achieve a surface density of min 70kg/m2	Wood Flooring on CLT 20x63x800-1200mm Smoaked Oak, long block, as Hörning floor, quality select, surface Charcoal Black oil. 10 glue / levelling 120 mm CLT Steel substructure acc. to contractor (fixed to main steel beams) Total density min. 70 kg/m2	Charcoal black oil, smoked solid oak	 Hørning Parket A/S
	Stalls floor	F23B	Wood Flooring on stalls solid smoked oak parquet, charcoal oil 20x63x800-1200mm Adhesive 5mm Extra concrete if machinery cannot achieve weight the machinery below ACC to information from consultants and producers	AR-014222 AR-015640 AR-015200	yes	Smoaked Oak solid wood floor, long block, mounted on theatre equipement.	All layers must be bonded to the structure tightly and continuously into one solid monolithic body, with no air gaps or bubbles between layers. The resulting complex should achieve a surface density of min 70kg/m2	Wood Flooring on stalls 20x63x800-1200mm Smoaked Oak, long block, as Hörning floor, quality select, surface Charcoal Black oil.	Charcoal black oil, smoked solid oak	 Hørning Parket A/S Christiansmindevej 12 DK-8660 Skanderborg +45 7027 6600 sales@horningfloor.dk https://www.horningfloor.dk/?lang=en Contact person: Jacob Schedler js@horningfloor.dk Monocoat oil https://www.rubiomonocoat.com/en?reset&country=aa
	Orchestra Pit	F24A	Wood Flooring for Orchestra pit Decking 45mm (8mm Hardwood Accordign to theater consultatn 29mm Softwood core (According to acoustic specs) (8mm Hardwood Accordign to theater consultatn 45x45mm Softwood sleepers c/c300mm 90x90mm Softwood Beams c/c900mm 20mm Air void / Joist levelers Vapour barrier	AR-015200 015521	AR- yes	Hardwood black Accordign to theater consultant	See: Nagata, Appendix D Construction Requirements and Recommendations Room Acoustics, Performance Spaces	Orchestra pit mounted wither on structural concrete or stalls machinery.	RAL9005.	
	Level 00 inside Hall	F24B	Wood Flooring on Screed solid smoked oak parquet, charcoal oil 20x63x800-1200mm adhesive/membrane and levelling 10mm screed 70mm rigid insulation 50mm	AR-014222 AR-015200	yes	Smoaked Oak solid wood floor, long block, 10mm glue(levelling layer, mounted on screed.	All layers must be bonded to the structure tightly and continuously into one solid monolithic body, with no air gaps or bubbles between layers. The resulting complex should achieve a surface density of min 70kg/m2	Wood Flooring on Screed 20x63x800-1200mm Smoaked Oak, long block, as Hörning floor, quality select, surface Charcoal Black oil. 10 glue / levelling 70mm Screed 50mm Rigid insulation Total density min. 70 kg/m2	Charcoal black oil, smoked solid oak	 Hørning Parket A/S
	Light Position rooms / side of front stage	F25B	Wood Flooring on Structural Concrete solid smoked oak parquet, charcoal oil 20x63x800-1200mm adhesive/membrane and levelling 10mm Structural concrete	AR-014223-224 AR-015200	yes	Smoaked Oak solid wood floor, long block, 10mm glue (levelling layer, mounted on Strucutral Concrete.	All layers must be bonded to the structure tightly and continuously into one solid monolithic body, with no air gaps or bubbles between layers. The resulting complex should achieve a surface density of min 70kg/m2	Wood Flooring on Screed 20x63x800-1200mm Smoaked Oak, long block, as Hörning floor, quality select, surface Charcoal Black oil. 10 glue / levelling Strucutral concrete Total density min. 70 kg/m2	Charcoal black oil, smoked solid oak	 Hørning Parket A/S
	Sound Mix Floor Finish	F27B	SOLID SMOKED OAK PARQUET, CHARCOIL OIL, 20 X 65 X 800-1200 MM ADHESIVE 4 MM FLOOR BUILDUPS AS PER DUCKS SPECIFICATION	AR-014194	yes		All layers must be bonded to the structure tightly and continuously into one solid monolithic body, with no air gaps or bubbles between layers. The resulting complex should achieve a surface density of min 70kg/m2		Charcoal black oil, smoked solid oak	 Hørning Parket A/S
	Sound locks	F03C	Carpet flooring carpet, colour charcoal 100% polyamide ultra soft adhesive and leveling 10mm screed 80mm insulation rigid 50mm	AR-014222-224	yes	carpet			colour charcoal	 Van Besouw Van Besouw B.V. Sasdiijk 14 8281 BM Genemuiden T +31 (0)38 385 8818 M info@besouw.nl https://besouw.nl/en/
	Control room floor	F06A	Raised floor, Antistatic carpet antistatic (600x600mm) Colour black, 5mm raised floor, load capacity 500n/m2 Access plates and location of cable trays acc.	AR-014222 AR-015200	yes/no	raised system floor, surface carpet.	antistatic finish 500 daN/m² capacity	Raised floor system like Gamaflor PAC, 600x600, with reinforced pedestals like ATH900. Surface like Polygroup Rock Carpet. Carpet tiles 600x600 Raised floor, up 1100 mmwith cablestrays 200 mm under top Load capacity 500 daN/m²	Black - for Rock carpet No 410.	
	Follow Spot Room/Storage Room Floor	F04A	Eco Friendly Silicate Based Flooring Thickness:150mm eco friendly silicate based coating, 10mm screed, 70mm Rigid Insulation 60mm	AR-014222-225 AR-015200	yes	silicate based flooring			dark	
		F04E	Eco Friendly Silicate Based Flooring Thickness:30mm eco friendly silicate based coating, 10mm Leveling 20mm	AR-014223-225 AR-015200						
	Inside hall Side for stage floor extension	F08C	Stage Flooring inside hall solid smoked oak parquet, charcoal oil 20x63x800-1200mm (according to theater consultant) adhesive/membrane and levelling 10mm screed 70mm rigid insulation 100mm	AR-014222 AR-015200	yes	Smoaked Oak solid wood floor, long block, 10mm glue(levelling layer, mounted on Strucutral Cncrete.	All layers must be bonded to the structure tightly and continuously into one solid monolithic body, with no air gaps or bubbles between layers. The resulting complex should achieve a surface density of min 70kg/m2	Wood Flooring on Screed 20x63x800-1200mm Smoaked Oak, long block, as Hörning floor, quality select, surface Charcoal Black oil. 10 glue / levelling Strucutral concrete Total density min. 70 kg/m2	Charcoal black oil, smoked solid oak	 Hørning Parket A/S

Issued for Construction - Mid Scale Theatre - Material Schedule

0. All interior finishes shall comply with Table 803.3, SBC 801
1. All reference manufacturers, brands and products are representative of the design intent as referenced in the design drawings, specifications, schedules and reports. They may be substituted under a Contractor's Proposal provided that they are accepted by the Designers and that they conform to any specified performance requirements.
2. All divergence from the reference products/ materials are to be formally notified in writing to the designer. The Designer shall have not less than 10 working days to respond to all proposals. The Designer reserves the right to reject the proposed alternative product or material.
3. All suggested alternative samples are to be issued to the Designer for review at least 10 working days prior to the submission of a formal Contractor's Proposal. Acceptance of the sample by the Designer does not relieve the Contractor of conformance of the installation works to the Design Intent.
4. Image swatches are indicative only and are not to be used for colour matching, sampling, or benchmarking.
5. Refer to the design drawings for locations of finishes.

Date 31.1.2024

Rev.Date 31.1.2024

Rev. No. F00

MID-SCALE THEATRE - Material Schedule

TYPE	NAME	RVT	DRAWING	visible	material	density / acoustic requirement	description	treatment/color	picture	contact
	Gallery Level/Proscenium Lighting Position	F08B	Vinyl Plywood Flooring According to information from Theater Consultants	AR-014225 AR-015200	yes/no	Vinyl on Plywood flooring	All Cable racks, access hatches or visible equipment supported on lighting galleries should be painted black . Color: RAL 9005	black RAL 9005		
		F09B	GRP Grill Flooring According to information from Theater Consultants	AR-014225 AR-015200	yes/no	GRP Grating on steel structure				
CEILINGS	Balcony Soffits	SC53	Balcony soffits: Black ash veneer plywood (MT) Total build up 125mm 45x70mm C profiles C/C Max 300mm 25mm Hatprofile C/C max 300mm 2x12.5mm Gypsumboard (min 30kg/m2) 4mm Plywood (between mounting brackets) 12mm+1mm veneered black as plywood	AR-014210-11	yes	Black stained ash wood veneer (visible surface) on Plywood. Hidden mounted on gypsum ceiling.	All layers must be bonded to the structure tightly and continuously into one solid monolithic body, with no air gaps or bubbles between layers. The resulting complex should achieve a surface density of min 30kg/m2	12 mm plywood with ash veneer, stained black, Hidden mounting as Gustafs Capax, remaining void 4mmn plywood, 3 layers of gypsum,25 mm hatprofiles, fastened to C-profiles, 70mm, mounted on steel substructure to be calculated by Contractor	Fire retardant treated to class C, 100 % transparent Varnish, ultra matte, gloss 2. Veneer quality, as linear as possible: - Quarter cut - Slip matched	JJI inventar JJi Akustik & Inventar A/S
	Access hatches in soffit			AR-015620	yes	plywood. Veneer to be defined	All layers must be bonded to the structure tightly and continuously into one solid monolithic body, with no air gaps or bubbles between layers. The resulting complex should achieve a surface density of min 30kg/m2	Flush mounted fire access gypsum hatch with inlay of 2 layers 15mm fibre gypsum. Hidden behind removable soffit panel.	black	
	Technical channels	UP01			yes	Blued steel profile		3mm steel plate, cut to follow soffit radius. 100 and 150mm width. 170x160x2mm L steel profile towards AW20 walls.	Blued steel	
	Acoustic ceiling	SC71	Solid Precast Fiber Cement Panels (GRC) Double curved straight sphere D1200mm with 300mm slag Total build up min. 120mm Elements with tongue and groove connections mounted on steel substructure to be calculated by contractor see acoustic report for ceiling variations in geometry	AR-015621	yes/no	fibre cement panels, precast, curved / double curved	min. 60kg/m2	Acoustic Ceiling, Solid GRC Thickness min. 30 mm to achieve (min. 60kg/m2) Double curved Elements with tongue and groove connections Mounted on steel substructure to be calculated by contractor See acoustic report for wall variations in geometry	Fire Class C acc. ASTM E84 Dark Grey	
	Sound locks	SC34	Black Metal Lamella Ceilings 50% Open Total build up 120mm 50mm black sound insulation attached bottom of slab 45mm black primary/40mm black secondary T profiles 25 mm black lamella clip in profiles 75x100mm black metal lamellas	AR-014210-11	yes	steel			heat treated steel black colour	
	Control room ceiling	SC11b	Demountable Acoustic Ceiling System Ceiling with Seamless Edges 600x600mm total build up 60mm main runner and cross tees 38mm hidden clip-in system stone wool tiles 600x600mm - 22mm with seamless edge/hidden clip	AR-015100 014170 014271	AR- AR- yes	plaster finish on mineral wool panels	class C or better		black	
	Architectural ceiling	SC35	Architectural Ceiling (Acoustically Transparent) Brushed Brass, 25mm x 25mm, varied spacing according to design intention Mounted on bend steelframe acc. To contactor Frames mounted on bend steel profiles acc. To contactor	AR-015621 AR-015100	yes	Brushed brass	acoustically transparent with min. 60% openness. Any deviation from the design affecting opening ratio, size or distribution of solid elements to be submitted to acoustician fore review and aproval	Brushed brass profiles with irregular c-c, ca 17pcs pr m, fastened to rolled profile with screws from top. , 25x25, structure acc to contractor all elements to be fixed tightly and contacts to be treated with soft non-porous material to prevent rattling and vibrations	brushed brass	
	Orchestra Pit - Soffit	SC54	Orchestra Pit Soffit, Painted Black 2 x 15 mm Plywood (painted black) 70 mm C-profile / stud c/c max 450mm (min. 15 kgm2)	AR-015101 015521	AR- yes	plywood	All layers must be bonded to the structure tightly and continuously into one solid monolithic body, with no air gaps or bubbles between layers. The resulting complex should achieve a surface density of min 15kg/m2		black RAL 9005	
	Lighting gallery and forestage	SC53	Balcony soffits: Black ash veneer plywood (MT) Total build up 125mm 45x70mm C profiles C/C Max 300mm 25mm Hatprofile C/C max 300mm 3x12.5mm Gypsumboard (min 30kg/m2) 4mm Plywood (between mounting brackets) 12mm+1mm veneered black as plywood	AR-015101 AR-015620	yes/no	Grating on steel structure	All layers must be bonded to the structure tightly and continuously into one solid monolithic body, with no air gaps or bubbles between layers. The resulting complex should achieve a surface density of min 30kg/m2	All Cable racks, access hatches or visible equipment supported on lighting galleries should be painted black . Color: RAL 9005	black RAL 9005	
WINDOWS	Control room window				yes	Two acoustic sliding windows on both sides, center window fixed with special glas for projection acc to dUCKS (Vision LITE STADIP PROTECT from saint gobain) Laminated glass interior/exterior 45dB RW according to Acoustic report (BH)	See BHE Acoustic Report 00H-BHC-S4-01-056-XXX-DS-TCR-AC-0004	Three window units: two sliding windows on each side and smaller center window fixed for projection. Each window unit consists of one vertical window towards the control room and one -6 degrees tilted window towards the hall. Custom made acoustic window to fulfil the acoustic requirements.	Frame blued steel, rails black RAL9005.	
STAIR	Steps, step sides, Nosing	F24B F25B		AR-015640	yes	Steps same as floor, step sides and nosing	Min. surface density requirement of 70kg/m2 fulfilled under steps	Steps with same wooden floor as flooring. Pattern to follow overall wood floor pattern/direction. Step nosing 40x20mm solid smoked oak with 2x solid brass inlay 3mm, same wood and treatment as floor.	Same treatment as wooden floor	
	Loop rails, handrails, guardrails			AR-015640 AR-015600	yes	ø30mm steel, bent	Strength requirement acc to contractor	Handrails mounted to structure for AW20 wall.	Blued steel	

Issued for Construction - Mid Scale Theatre - Material Schedule

0. All Interior finishes shall comply with Table 803.3, SBC 801
1. All reference manufacturers, brands and products are representative of the design intent as referenced in the design drawings, specifications, schedules and reports. They may be substituted under a Contractor's Proposal provided that they are accepted by the Designers and that they conform to any specified performance requirements.
2. All divergence from the reference products/ materials are to be formally notified in writing to the designer. The Designer shall have not less than 10 working days to respond to all proposals. The Designer reserves the right to reject the proposed alternative product or material.
3. All suggested alternative samples are to be issued to the Designer for review at least 10 working days prior to the submission of a formal Contractor's Proposal. Acceptance of the sample by the Designer does not relieve the Contractor of conformance of the installation works to the Design Intent.
4. Image swatches are indicative only and are not to be used for colour matching, sampling, or benchmarking.
5. Refer to the design drawings for locations of finishes.

MID-SCALE THEATRE - Material Schedule											
TYPE	NAME	RVT	DRAWING	visible	material	density / acoustic requirement	description		treatment/color	picture	contact
CURTAIN BOXES	Curtain boxes to store curtains	AW13A SC56 F30A	Curtain Boxes Min 15kg/m2 (15mm Plywood (Painted Black) Adhesive 15mm Plywood) RHS frame strucutre accoring to contractor	AR-014291 AR-015200 AR-015004 AR-015101	no/yes	plywood	All layers must be bonded to the structure tightly and continuously into one solid monolithic body, with no air gaps or bubbles between layers. The resulting complex should achieve a surface density of min 15kg/m2		Plywood (painted black) on RHS framework	black RAL 9005	
OTHERS	Steel work behind A.T. Walls			AR-014290	no/yes	Steel profiles. Halfen HZM 41x41 to attach the wall to and 50x50x5mm RHS profile behind as structure, RHS acc to contractor	Halfen HZM 41x41 welded to RHS profile. RHS profile fastened to structure in top and bottom.		Profile including all fasteners have to be painted black RAL9005, matte finish.		
	Acoustic curtain along the auditorium wall under curtain track	-			yes	Textile	min. Density 0.5 kg/m2 of drapery 100% fullness (total min density 1kg/m²)		Fabric to be tested acc. To ISO 354:2003	Alicante Color to match Gerriets Alicante Light beig	Gerriets
	Curtain of acoustics banners	-			yes	Textile	min. Density 0.5 kg/m2 of drapery 2 layers, flat (total min density 1kg/m²)		Fabric and banner to be tested acc. To ISO 354:2003	Abrosber CS Color: Dark Grey	Gerriets

JEDDAH OPERA
Issued for Construction - Rehearsal Hall - Material Schedule

Date31.1.2024

Rev.Date31.1.2024
Rev. No.F00

0. All Interior finishes shall comply with Table 803.3, SBC 801
1. All reference manufacturers, brands and products are representative of the design intent as referenced in the design drawings, specifications, schedules and reports. They may be substituted under a Contractor's Proposal provided that they are accepted by the Designers and that they conform to any specified performance requirements.
2. All divergence from the reference products/ materials are to be formally notified in writing to the designer. The Designer shall have not less than 10 working days to respond to all proposals. The Designer reserves the right to reject the proposed alternative product or material.
3. All suggested alternative samples are to be issued to the Designer for review at least 10 working days prior to the submission of a formal Contractor's Proposal. Acceptance of the sample by the Designer does not relieve the Contractor of conformance of the installation works to the Design Intent.
4. Image swatches are indicative only and are not to be used for colour matching, sampling, or benchmarking.
5. Refer to the design drawings for locations of finishes.

Rehearsal Hall											
TYPE	NAME	RVT		DRAWING	visible	material	density / acoustic requirement	description	treatment/color	picture	Supplier/contact
WALLS	Architectural walls and skirting	IW32	Build up: Acc. to Keynote TOTAL THICKNESS: 180 MM WOOD VENEER PANELS, AMERICAN WALNUT ON PLYWOOD, VARNISHED 180 MM WALNUT VENEER WOOD FRAME PANELS WITH EMBEDDED WALNUT VENEER LAMELLAS 100/45MM ACOUSTICALLY TRANSPARENT WITH OPENING RATIO APP. 60% REQUIREMENTS ACC. TO NAGATA ROOM ACOUSTICS REPORT STRUCTURE METAL FRAMING SYSTEM SUPPORT AS UNISTRUT OR SIMILAR FIRE: CLASS C	AR-014301 AR-014302 AR-014331 AR-014393	yes	Wood - American Walnut	Density / Acoustic requirement: Acoustic transparent min. 50 %	Architectural Wooden wall panel Wood veneer panel, all visible surface american walnut. All visible edges massive american walnut. Veneer applied parrallel to vertical direction. Veneersheets to be mixed to avoid mirrow effect. Veneer to be provided by same supplier for all wooden panel Fire code: Fire classification Class C all elements to be fixed tightly and contacts to be treated with soft non-porous material to prevent rattling and vibrations	Surface treatment: Varnish to be 100 % transparent, ultra matte, gloss 2. 2 x lacquer type AB19, which is part of the full fire classification. 1 x Clear lacquer, gloss 2		JJI inventar JJI Akustik & Inventar A/S info@jji.as +45 4483 0208 Baltorpbakken 5 DK-2750 Ballerup https://www.jji.as/in-sign-akustik Contact person: Janna Linn Grunth <jlg@jji.as>
	Architectural walls and skirting	IW36	Build up: Acc. to Keynote Total build up 45 mm Wooden veneered panels, american walnut on plywood, 45 mm walnut veneered wooden frame panels with embedded walnut veneered lamellea 45 mm Structure metal framing system support as unistrut / Halfen	AR-014301 AR-014302 AR-014331 AR-014393	yes	Wood - American Walnut	Density / Acoustic requirement: Acoustic transparent min. 50 %	Architectural Wooden wall panel Wood veneer panel, all visible surface american walnut. All visible edges massive american walnut. Veneer applied parrallel to vertical direction. Veneersheets to be mixed to avoid mirrow effect. Veneer to be provided by same supplier for all wooden panel Fire code: Fire classification Class C all elements to be fixed tightly and contacts to be treated with soft non-porous material to prevent rattling and vibrations	Surface treatment: Varnish to be 100 % transparent, ultra matte, gloss 2. 2 x lacquer type AB19, which is part of the full fire classification. 1 x Clear lacquer, gloss 2		JJI inventar JJI Akustik & Inventar A/S info@jji.as +45 4483 0208 Baltorpbakken 5 DK-2750 Ballerup https://www.jji.as/in-sign-akustik Contact person: Janna Linn Grunth <jlg@jji.as>
	Acoustic shaping wall surface - absorbtive	AW32	Build up: Acc. to Keynote Total build up 55 mm 6 mm magnetic fixing device 49 mm Fabric tensioned on aluminium frame with absorbtive softboard material integrated	AR-014301 AR-014302 AR-014332	yes	Fabric	Density / Acoustic requirement: Acoustic Absorbtive Class A	Wall panel - acoustic absorbtive, soft cell. Fabric tensioned on aluminium frame with acoustic absorbant material behind. Fabric Kvadrat, Casa 212, Trevira CS Fire code: Fire classification Class B	Surface treatment: -		Kvadrat acoustic Kvadrat A/S Pakhus 48 Klubiensvej 22, Frihavnen 2150 Nordhavn, Denmark https://www.kvadrat.dk/en/kvadrat-acoustics Contact person: Jesper Vangby Country Director M +45 3080 2216
	Acoustic shaping wall structure - reflective	AW30	Build up: Acc. to Keynote Total Buildup 38 mm 25 mm prefab fiber concrete wall (custom geometry 3 mm tile glue (IW27) 10 mm natural stone (IW27) Prefab wall supports and montage principle defined by supplier	AR-014301 AR-014302 AR-014332	no	Fiber concrete	Density / Acoustic requirement: min 30kg/m2	Concret wall cladding elements - acoustic shaping. Fiber Concrete, Solid wall, Fibre concrete with custom geometry. Oyster white RAL 1013, BBf No. 03-S Fire code: Fire classification Class C	Surface treatment: Tiles applied. See below		BB Fiberbeton / Fiber concrete www.bbfiberbeton.dk/en https://www.bbfiberbeton.dk/en/contact Contact person: Helene Bieger helene@bbfiberbeton.dk
	Acoustic wall finish on acoustic shaping wall - reflective	AW30 IW27	Build up Acc. To keynote Total thickness13 mm 3 mm tile glue 10 mm natural stone	AR-014301 AR-014302 AR-014333	yes	Natural stone - Coral stone/sand stone	Density / Acoustic requirement: min 30kg/m2 for the entire wall build up.	Wall finish on acoustic shaping wall - acoustic reflective Natural stone tiles similar to 1. Sand stone, Coral white (oryx) oman or 2. Sohar antique, honed White beige Sizes acc. to drawing Width:120/400 mm Length:600/1200/1720 Fire code: Fire classification Class C	Surface treatment: Honed		Moser & Moser https://moserogmoser.dk/contact/ https://moserogmoser.dk/project-ksa1/ Contact Person: Susan Moser Office: +45 5353 4422 Direct: +45 2122 3276 Email: info@moserogmoser.dk
	Acoustic wall finish - absorbtive (technical floor)	AW33	Build up Acc. To keynote	AR-014333	only at technical floor level	Mineral wool	Density / Acoustic requirement: Sound absorption Class A	Wall panel - acoustic absorbtive Mineral wool consealed in fabric cover or similar. 50mm-thick, with medium density (20-60kg/m³). Black Fire code: Fire classification Class C	Surface treatment/color: Black		not informed

JEDDAH OPERA
Issued for Construction - Rehearsal Hall - Material Schedule

0. All Interior finishes shall comply with Table 803.3, SBC 801
1. All reference manufacturers, brands and products are representative of the design intent as referenced in the design drawings, specifications, schedules and reports. They may be substituted under a Contractor's Proposal provided that they are accepted by the Designers and that they conform to any specified performance requirements.
2. All divergence from the reference products/ materials are to be formally notified in writing to the designer. The Designer shall have not less than 10 working days to respond to all proposals. The Designer reserves the right to reject the proposed alternative product or material.
3. All suggested alternative samples are to be issued to the Designer for review at least 10 working days prior to the submission of a formal Contractor's Proposal. Acceptance of the sample by the Designer does not relieve the Contractor of conformance of the installation works to the Design Intent.
4. Image swatches are indicative only and are not to be used for colour matching, sampling, or benchmarking.
5. Refer to the design drawings for locations of finishes.



Plan A



BURO HAPPOLD



Henning
Larsen

Date

31.1.2024

Rev.Date

31.1.2024

Rev. No.

F00

Rehearsal Hall											
TYPE	NAME	RVT		DRAWING	visible	material	density / acoustic requirement	description	treatment/color	picture	Supplier/contact
	Wall panel, towards doors inside hall, level 00, level 01	IW25	Build up Acc. To keynote Thickness 25 mm 25 mm Wooden veneered panel american walnut xx mm substructure	AR-014301 AR-014331 014393	yes	Wood - Americal walnut	Density / Acoustic requirement: min 15kg/m2	Architectural Wooden wall panel door niches. Wood veneer panel, all visible surface american walnut. All visible edges massive american walnut. Veneer aplied parrallel to vertical direction. Veneersheets to be mixed to avoid mirrow effect. Veneer to be provided by same supplier for all wooden panel Fire code: Fire classification Class C	Surface treatment: Varnish to be 100 % transparent, ultra matte, gloss 2. 2 x lacquer type AB19, which is part of the full fire classification. 1 x Clear lacquer, gloss 2		JJI inventar JJi Akustik & Inventar A/S info@jji.as +45 4483 0208 Baltorpbakken 5 DK-2750 Ballerup https://www.jji.as/in-sign-akustik Contact person: Janna Linn Grunth <jlg@jji.as>
	Wall panel on semi wall, enclosure of the mixing desk position	IW34 IW35	Build up Acc. To keynote Total build up 124 mm 100 mm metal stud 12 mm plywood 12 mm wooden veneered panel american walnut	AR-014301 AR-014302 AR-014331 AR-014393	yes	Wood - Americal walnut	Density / Acoustic requirement: Acoustic transparent min. 30 % (IW35) Sound absorption Class A (between IW34 and IW35)	Architectural Wooden wall panel on mixing desk position Wood veneer panel, all visible surface american walnut. All visible edges massive american walnut. Veneer aplied parrallel to vertical direction. Veneersheets to be mixed to avoid mirrow effect. Veneer to be provided by same supplier for all wooden panel Fabric Kvadrat, Casa 212, Trevira CS mounted to the backside of the panel to allow sound absorbtion from the mineral wool behind IW34 Fire code: Fire classification Class C	Surface treatment: Varnish to be 100 % transparent, ultra matte, gloss 2. 2 x lacquer type AB19, which is part of the full fire classification. 1 x Clear lacquer, gloss 2		JJI inventar JJi Akustik & Inventar A/S info@jji.as +45 4483 0208 Baltorpbakken 5 DK-2750 Ballerup https://www.jji.as/in-sign-akustik Contact person: Janna Linn Grunth <jlg@jji.as>
	Wall panels - sound lock	IW27	Build up Acc. To keynote Total build up 13 mm 3 mm tile glue 10 mm natural stone	AR-014301 AR-014302 AR-014351	yes	Natural stone - Coral stone/sand stone	Density / Acoustic requirement: min 30kg/m2 fot the entire wall build up.	Wall finish on sound lock walls Natural stone tiles similar to 1. Sand stone, Coral white (oryx) oman or 2. Sohar antique, honed White beige Sizes acc. to drawing. Width: 1200 Lenght: 900/1200 Fire code: Fire classification Class C	Surface treatment: Honed		Moser & Moser https://moserogmoser.dk/contact/ https://moserogmoser.dk/project-ksa1/ Contact Person: Susan Moser Office: +45 5353 4422 Direct: +45 2122 3276 Email: info@moserogmoser.dk
	Wall panel/downstand on telescopic tribune	Theatre consultant Ducks	Build up Acc. To keynote	AR-014351	yes	Wood - Americal walnut	Density / Acoustic requirement: Acoustic transparent min. 30 % Panels perforatated with rectangular holes; hole diameter 8 mm vertical slots 140-180 mm dependant on panel height, distance between holes 16 mm, perimeter boarder 60 mm top, bottom and side of panel.	Wall panel on tribune Wood veneer panel, all visible surface american walnut. All visible edges massive american walnut. Veneer aplied parrallel to vertical direction. Veneersheets to be mixed to avoid mirrow effect. Veneer to be provided by same supplier for all wooden panel Fire code: Fire classification Class C / Bs-1d0	Surface treatment: Varnish to be 100 % transparent, ultra matte, gloss 2. 2 x lacquer type AB19, which is part of the full fire classification. 1 x Clear lacquer, gloss 2		JJI inventar JJi Akustik & Inventar A/S info@jji.as +45 4483 0208 Baltorpbakken 5 DK-2750 Ballerup https://www.jji.as/in-sign-akustik Contact person: Janna Linn Grunth <jlg@jji.as>
BALCONY FRONT	Balcony railing and gate, balustrate	RL50 RL51	Build up Acc. To keynote	AR-014373	yes	Steel	Not informed	Steel Railing balustrate 3 mm wire, stainless steel, Aisi 316, mounted with a turnbuckle. Wire is fed through e.g. zig/zag eye. Fire code: Fire classification Class C	Surface treatment: -		inox line, Jakob robe system https://inoxline.dk/en/jakob-rope-system https://inoxline.dk/en/macalloy/ INOXLINE Aps DK - 5000 Odense C Telephone: +45 7020 9840 Contact person: Stefan Hansen sh@inoxline.dk
	Balcony railing and gate, structure post and rail	RL50 RL51	Build up Acc. To keynote	AR-014373	yes	Steel	Not informed	Steel Railing post and rail Solid steel. Fire code: Fire classification Class C	Surface treatment: Painted , Black RAL 9011 /NCS 8500 N, gloss 2		not informed
	Balcony front cladding, at mixing desk position	RL52	Build up Acc. To keynote	AR-014373	yes	Wood - Americal walnut		Balcony front cladding: Solid steel. Fire code: Fire classification Class C	Surface treatment: Painted , Black RAL 9011 /NCS 8500 N, gloss 2		not informed

JEDDAH OPERA
Issued for Construction - Rehearsal Hall - Material Schedule

Date31.1.2024

Rev.Date31.1.2024
Rev. No.F00

0. All Interior finishes shall comply with Table 803.3, SBC 801
1. All reference manufacturers, brands and products are representative of the design intent as referenced in the design drawings, specifications, schedules and reports. They may be substituted under a Contractor's Proposal provided that they are accepted by the Designers and that they conform to any specified performance requirements.
2. All divergence from the reference products/ materials are to be formally notified in writing to the designer. The Designer shall have not less than 10 working days to respond to all proposals. The Designer reserves the right to reject the proposed alternative product or material.
3. All suggested alternative samples are to be issued to the Designer for review at least 10 working days prior to the submission of a formal Contractor's Proposal. Acceptance of the sample by the Designer does not relieve the Contractor of conformance of the installation works to the Design Intent.
4. Image swatches are indicative only and are not to be used for colour matching, sampling, or benchmarking.
5. Refer to the design drawings for locations of finishes.

Rehearsal Hall											
TYPE	NAME	RVT		DRAWING	visible	material	density / acoustic requirement	description	treatment/color	picture	Supplier/contact
	Balcony front cladding	IW26	Build up Acc. To keynote	AR-014351 AR-014373	yes	Wood - Americal walnut	Density / Acoustic requirement: -	Wooden wall panel on balcony front Wood veneer panel, all visible surface american walnut. All visible edges massive american walnut. Veneer aplied parrallel to vertical direction. Veneersheets to be mixed to avoid mirrow effect. Veneer to be provided by same supplier for all wooden panel Fire code: Fire classification Class C	Surface treatment: Varnish to be 100 % transparent, ultra matte, gloss 2. 2 x lacquer type AB19, which is part of the full fire classification. 1 x Clear lacquer, gloss 2		JJI inventar JJi Akustik & Inventar A/S info@jji.as +45 4483 0208 Baltorpbakken 5 DK-2750 Ballerup https://www.jji.as/in-sign-akustik Contact person: Janna Linn Grunth <jlg@jji.as>
FLOORS	Floor finish on dance floor, leve 00	F21A, F21B, F21C, & Theatre consultant Ducks	Build up Acc. To keynote Total thickness 20 mm 20 mm solid wooden floor 80 mm dancefloor build up acc. To theater consult.	AR-014301	yes	Wood - Smoked oak	Not informed	Wooden Flooring on stage floor/dancefloor buildup level 00 Wood, solid wood, smoked oak Plank, thickness 20 mm, width 100 mm x various length min. 600/900/1200/1500/1800 mm Density requirement Acc. theater consultant Fire code -	Surface treatment: Surface treatment black oil as Rubio Monocoat Oil plus 2C, Black, ultra mat.		Hørning Parket A/S Christiansmindevej 12 DK-8660 Skanderborg +45 7027 6600 sales@hørningfloor.dk https://www.hørningfloor.dk/?lang=en Contact person: Jacob Schedler js@hørningfloor.dk Monocoat oil https://www.rubiomonocoat.com/en?reset&country=aa
	Floor finish, Balcony floor level 01	F20A,	Build up Acc. To keynote Total build up 150 mm 20 mm solid wooden floor 10 mm adhesive and leveling 120 mm concrete/screed	AR-014302	yes	Wood - Smoked oak	Density requirement Min. surface density requirement of 70kg/m2 - to be met by the total build-up (finish + underlay) with no void.	Wooden Flooring on balcony Wood, solid wood, smoked oak Plank, thickness 20 mm, width 100 mm x various length min. 600/900/1200/1500/1800 mm Fire code -	Surface treatment: Surface treatment black oil as Rubio Monocoat Oil plus 2C, Black, ultra mat.		Hørning Parket A/S Christiansmindevej 12 DK-8660 Skanderborg +45 7027 6600 sales@hørningfloor.dk https://www.hørningfloor.dk/?lang=en Contact person: Jacob Schedler js@hørningfloor.dk Monocoat oil https://www.rubiomonocoat.com/en?reset&country=aa
	Floor finish, Retractable tribune	Theatre consultant Ducks	Build up Acc. To keynote Total thickness 20 mm 20 mm solid wooden floor	AR-014301 AR-014302	yes	Wood - Smoked oak	Density requirement Min. surface density requirement of 70kg/m2 - to be met by the total build-up (finish + underlay) with no void.	Wooden Flooring on telescopic tribune level 00-01 Wood, solid wood, smoked oak Plank, thickness 20 mm, width 100 mm x various length min. 600/900/1200/1500/1800 mm Fire code -	Surface treatment: Surface treatment black oil as Rubio Monocoat Oil plus 2C, Black, ultra mat.		Hørning Parket A/S Christiansmindevej 12 DK-8660 Skanderborg +45 7027 6600 sales@hørningfloor.dk https://www.hørningfloor.dk/?lang=en Contact person: Jacob Schedler js@hørningfloor.dk Monocoat oil https://www.rubiomonocoat.com/en?reset&country=aa
	Floor finish, Circulation area next to wiregrid floor, Level 02	F09C	Build up Acc. To keynote	AR-014303	yes	Wiregrid - tensioned	Not informed	Steelgrating level 02 Steel grating 70 mm Masking 70x20x20 mm	Surface: Galvanized / Painted , Black RAL 9011		Not informed
	Sound locks	F03B	Build up Acc. To keynote Total build up 150 mm 10 mmm carpet 10 mm adhesive and leveling 130 mm concrete/screed	AR-014301 AR-014302	yes	Carpet	Not informed	Carpet flooring level 00-01 Tufted carpet, 100% polyamide ultra soft AS Van besouw 2609-050 synthetisch, 10 mm thickness 1666 g/m2 Fire code: Cfl-S1 / Class B	Surface: Tufted, color whitebeige		Van Besouw Van Besouw B.V. Sasdjik 14 8281 BM Genemuiden T +31 (0)38 385 8818 M info@besouw.nl https://besouw.nl/en/
		Main ceiling	Theatre consultant	Build up	AR-014313	yes	Steel wire	Acc. To Theater consultant	Wiregrid ceiling	Surface:	

JEDDAH OPERA
Issued for Construction - Rehearsal Hall - Material Schedule

0. All Interior finishes shall comply with Table 803.3, SBC 801
1. All reference manufacturers, brands and products are representative of the design intent as referenced in the design drawings, specifications, schedules and reports. They may be substituted under a Contractor's Proposal provided that they are accepted by the Designers and that they conform to any specified performance requirements.
2. All divergence from the reference products/ materials are to be formally notified in writing to the designer. The Designer shall have not less than 10 working days to respond to all proposals. The Designer reserves the right to reject the proposed alternative product or material.
3. All suggested alternative samples are to be issued to the Designer for review at least 10 working days prior to the submission of a formal Contractor's Proposal. Acceptance of the sample by the Designer does not relieve the Contractor of conformance of the installation works to the Design Intent.
4. Image swatches are indicative only and are not to be used for colour matching, sampling, or benchmarking.
5. Refer to the design drawings for locations of finishes.

Rehearsal Hall											
TYPE	NAME	RVT		DRAWING	visible	material	density / acoustic requirement	description	treatment/color	picture	Supplier/contact
CEILINGS		Ducks SC36	Acc. To keynote					Tensioned wiregrid Build up: Acc. to theater consultant deliverables	Painted , Black RAL 9011 / NCS 8500 N		
	Balcony ceiling, reflective, level 0	SC81	Build up Acc. To keynote Total build up 64 mm 27 mm load bearing profile 2x12,5 mm fiberboard 12 mm veneered wooden panel	AR-014311	yes	Wood - American Walnut	Density / Acoustic requirement: min 30kg/m2	Wooden ceiling panel under balcony level 0 - acoustic reflective. Wood veneered ceilingpanel, all visible surface american walnut. All visible edges massive american walnut. Veneer applied parrallel to vertical direction. Veneersheets to be mixed to avoid mirrow effect. Veneer to be provided by same supplier for all wooden panel Fire code: Fire classification Class C	Surface treatment: Varnish to be 100 % transparent, ultra matte, gloss 2. 2 x lacquer type AB19, which is part of the full fire classification. 1 x Clear lacquer, gloss 2		JJI inventar JJi Akustik & Inventar A/S info@jji.as +45 4483 0208 Baltorpbakken 5 DK-2750 Ballerup https://www.jji.as/ln-sign-akustik Contact person: Janna Linn Grunth <jlg@jji.as>
	balcony ceiling, acoustic transparent, level 1	SC82A SC82B	Build up Acc. To keynote Total build up 42 mm 27 mm load bearing profile 1 mm acoustic transparent fabric between panel and substructure 15 mm veneered wooden panel with perforation	AR-014312	yes	Wood - American Walnut	Density / Acoustic requirement: Acoustic transparent and min 30kg/m2 Panels perforatated with rectangular holes; hole diameter 8 mm vertical slots 140-180 mm dependant on panel height, distance between holes 16 mm, perimeter boarder 60 mm top, bottom and side of panel.	Wooden ceiling panel above balcony leve 01 - acoustic transparent Wood veneered ceilingpanel, all visible surface american walnut. All visible edges massive american walnut. Veneer applied parrallel to vertical direction. Veneersheets to be mixed to avoid mirrow effect. Veneer to be provided by same supplier for all wooden panel. Acoustic transparent fabric between panel and substructure Fire code: Fire classification Class C	Surface treatment: Varnish to be 100 % transparent, ultra matte, gloss 2. 2 x lacquer type AB19, which is part of the full fire classification. 1 x Clear lacquer, gloss 2 Fabric colour black		JJI inventar JJi Akustik & Inventar A/S info@jji.as +45 4483 0208 Baltorpbakken 5 DK-2750 Ballerup https://www.jji.as/ln-sign-akustik Contact person: Janna Linn Grunth <jlg@jji.as>
	Ceiling, towards doors inside hall, acoustically transparent, level 00	SC84	Build up: Acc. to Keynote Total build up 45 mm Wooden veneered panels, american walnut on plywood, 45 mm walnut veneered wooden frame panels with embedded walnut veneered lamellea 45 mm Structure metal framing system support as unistrut / Halfen	AR-014101 AR-014311	yes	Wood - American Walnut	Density / Acoustic requirement: Acoustic transparent min. 50 %	Architectural Wooden wall panel Wood veneer panel, all visible surface american walnut. All visible edges massive american walnut. Veneer applied parrallel to vertical direction. Veneersheets to be mixed to avoid mirrow effect. Veneer to be provided by same supplier for all wooden panel Fire code: Fire classification Class C	Surface treatment: Varnish to be 100 % transparent, ultra matte, gloss 2. 2 x lacquer type AB19, which is part of the full fire classification. 1 x Clear lacquer, gloss 2		JJI inventar JJi Akustik & Inventar A/S info@jji.as +45 4483 0208 Baltorpbakken 5 DK-2750 Ballerup https://www.jji.as/ln-sign-akustik Contact person: Janna Linn Grunth <jlg@jji.as>
	Ceiling, acoustic shaping reflective level 02	SC73	Build up Acc. To keynote	AR-014313	no	Concrete	Density / Acoustic requirement: min 60kg/m2	Concrete ceiling elements - acoustic reflective Fiber concrete elements, hemispheric custom geometry suspended from slab. Oyster white RAL 1013, BBf No. 03-S Fire code: Fire classification Class A	Surface treatment: Dust bound		BB Fiberbeton / Fiber concrete www.bbfiberbeton.dk/en https://www.bbfiberbeton.dk/en/contact Contact person:
	Ceiling, towards doors inside hall, level 00, level 01	SC55	Build up Acc. To keynote Total build up 25 mm 15 mm plywood 10 mm veneered plywood	AR-014311 AR-014312 AR-015700	yes	Wood - American Walnut	Density / Acoustic requirement: min 15kg/m2	Wooden ceiling panel door niches Wood veneer panel, all visible surface american walnut. All visible edges massive american walnut. Veneer applied parrallel to vertical direction. Veneersheets to be mixed to avoid mirrow effect. Veneer to be provided by same supplier for all wooden panel Fire code: Fire classification Class C	Surface treatment: Varnish to be 100 % transparent, ultra matte, gloss 2. 2 x lacquer type AB19, which is part of the full fire classification. 1 x Clear lacquer, gloss 2		JJI inventar JJi Akustik & Inventar A/S info@jji.as +45 4483 0208 Baltorpbakken 5 DK-2750 Ballerup https://www.jji.as/ln-sign-akustik Contact person: Janna Linn Grunth <jlg@jji.as>
	Sound lock acoustic ceiling - absorbtive Level 00 + level 01	SC41	Build up: Acc. To Keynote Total build up 55 mm 6 mm magnetic fixing device 49 mm Fabric tensioned on aluminium frame with absorbtive softboard material integrated	AR-014351 AR-014311 AR-014312		Fabric	Density / Acoustic requirement: Acoustic Absorbtive Class A	Fabric ceiling - acoustic absorbtive, soft cell. Fabric tensioned on aluminium frame with acoustic absorbant material behind. Fabric Kvadrat, Ginger 2 0122 to the front + Air 4 353 behind Fire code: Fire classification Class B	Surface treatment: -		Kvadrat acoustic Orient Plads 1, 2nd floorDK - 2150 Nordhavn, Copenhagen, Denmark kvadratacoustics@kvadrat.org +45 8953 1866 Contact person: Jesper Vagnby https://www.kvadrat.dk/en/kvadrat-acoustics

JEDDAH OPERA
Issued for Construction - Rehearsal Hall - Material Schedule

0. All Interior finishes shall comply with Table 803.3, SBC 801
1. All reference manufacturers, brands and products are representative of the design intent as referenced in the design drawings, specifications, schedules and reports. They may be substituted under a Contractor's Proposal provided that they are accepted by the Designers and that they conform to any specified performance requirements.
2. All divergence from the reference products/ materials are to be formally notified in writing to the designer. The Designer shall have not less than 10 working days to respond to all proposals. The Designer reserves the right to reject the proposed alternative product or material.
3. All suggested alternative samples are to be issued to the Designer for review at least 10 working days prior to the submission of a formal Contractor's Proposal. Acceptance of the sample by the Designer does not relieve the Contractor of conformance of the installation works to the Design Intent.
4. Image swatches are indicative only and are not to be used for colour matching, sampling, or benchmarking.
5. Refer to the design drawings for locations of finishes.

Rehearsal Hall											
TYPE	NAME	RVT		DRAWING	visible	material	density / acoustic requirement	description	treatment/color	picture	Supplier/contact
WINDOWS	Window towards facade	GW04	Build up: Acc. to Keynote	AR-014372	yes	Glass	Acoustic requirement: 55dB	Window unit - wide air spaced glazing system 2 separated single layered glass pane on each side of acoustic insulated spacer unit. Inner glass pane inclined/angled 5 degrees upwards. Outer glas pane vertical. Custom made acoustic window to fulfill the acoustic requirements.	Surface treatment: Window framing system powder coated, Black RAL 9011		
	Acoustic banners	acc. Theater consult.	Build up: Acc. to Keynote	AR-014333		Fabric	Density/Acoustic requirement min. Density 0,5 kg/m2 of drapery 2 layers, flat (total min density 1kg/m²)	Acoustic roller banner: Model Gerriets trevira CS Fabric and banner to be tested acc. To ISO 354:2003	Surface treatment: Trevira CS, Light grey, 1a541031		https://www.gerriets.com/
STAIR	Floor finish, stair, level 01 to tribune	Rehearsal Hall stair Level 1 to Retractable seating	Build up Acc. To keynote 20 mm steel 10/22 mm plywood 13/20 mm solid wood smoked oak Embedded step light	AR-014302 AR-014373	yes	Wood - Smoked oak	Density requirement Min. surface density requirement of 70kg/m2 - to be met by the total build-up (finish + underlay) with no void.	Wooden Flooring on stair level 01 Wood, solid wood, smoked oak Plank, thickness 20 mm, width 100 mm x various length min. 600/900/1200/1500/1800 mm Embedded steelbars at step edge Built in step light Fire code -	Surface treatment: Surface treatment black oil as Rubio Monocoat Oil plus 2C, Black, ultra mat.		Hørning Parket A/S Christiansmindevej 12 DK-8660 Skanderborg +45 7027 6600 sales@horningfloor.dk https://www.horningfloor.dk/?lang=en Contact person: Jacob Schedler js@horningfloor.dk Monocoat oil https://www.rubimonocoat.com/en?reset&country=aa
OTHERS	Steel work behind architectural walls and ceilings	LW30	Build up: Acc. to Keynote	AR-014333	yes			Halfen H2M 41x41 welded to RHS profile. RHS profile fastened to structure in top and bottom. Steel profiles. Halfen H2M 41x41 to attach the wall to and 50x50x5mm RHS profile behind as structure, RHS acc to contractor	Profile including all fasteners have to be painted black RAL9005, matte finish.		https://www.halfen.com/en_DE